

A-6-81

MAP NO. K-84

ELEV. 2878 DF

STATE Kansas COUNTY Seward SEC. 13 Twp 31 S Rge 33W

OPERATOR Peter Davis - Wichita, Kansas LOC. C SW/4

WELL NO. 1 FARM NAME Thompson FT. FROM _____ LINE _____


POOL Wildcat (PD 5900) FT. FROM _____ LINE _____

FR. 4-26-61 SPUD 4-25-61 COMP. 5-31-61 Pan Am support

CONT./GEOL. Lonita Oil Corp, tools Harvey Goffe/Geol

COMPLETION RECORD
NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a _____
b _____
c _____
d _____



a I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A D & A (XX)

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBD _____ TD 5897

CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8-5/8" 645 375 _____ _____ _____

OPERATOR Peter Davis WELL NO. 1 Thompson ELEV. 2878 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Winfield	2690		Chase	2564	
Topeka	3766		Council Grove	2931	
Heebner	4121		Missouri	4235	
Toronto	4141		Lansing	4276	
Lansing	4217		Des Moines	4870	
Marmaton	4869		Morrow	5372	
Morrow	5358		Chester	5457	
Chester	5532				
Ste Genevieve	5601				
St Louis	5678				

Spud 4-25-61. 8-5/8" @ 645 w/375 sx. @ 2900, moved in mud logging unit. Had SSO in samples fr 4217-21.

DST # 1 (Lans) 4303-43, op 1 hr, rec 150' M, ISIP 1360/30 mins, FP 55-85, FSIP 1300/30 mins.

DST # 2 (Marm) 4884-96, op 1 hr, rec 1350' GIP, 990' SW, ISIP 1520/30 mins, FP 190-450, FSIP 1345/30 mins.

DST # 3 (St L) 5715-77, op 45 mins, rec 60' M, ISIP 1715/30 min, FP 75-85, FSIP 1010/30 mins.

@ 5897, stk DP. RTD 5897, logs to 5500. (Logs were run through drill pipe) Rec DP. D & A COMPLETE 5-31-61

615223

LIBERAL TOPS

2878 DF

Winfield 2690 (+188)
Topeka 3766 (-888)
Heebner 4162 (-1284)
Toronto 4141 (-1263)
Lansing 4234 (-1356)
Marmaton 4869 (-1991) 5/5
Morrow 5358 (-2480) 5/9
Chester 5532 (-2654)
St. Gen 5601 (-2723)
St. Louis 5678 (-2800)

RTD 5897

D & A