


9-246W Map No. K-84 39b
 OPER CITIES SERVICE OIL S-T-R 6-31S-33W
LIBERAL, KS. SPOT C NW NE
 WELL #1 GUNN 'B' (Victory Lansing A) CO SEWARD, KS
 HOLM DRLG. ELEV 2949 KB
 FIELD VICTORY FIELD (MULTI-PAY)
 I.P. STATE POT: P 39 BOPD + 40% WTR, GR 40.2 DEG
LAN 4128-34



(KB LOG)

WIN	2664+	285
HB	4034-	1085
TOR	4056-	1107
LAN-A	4126-	1177
LAN-C	4406-	1457
LAN-D	4580-	1631
MAR	4760-	1811
LTD	4830-	1881
RTD	4830-	1881

SPUD 7-9-66 8" 612 W/350 SX.

DST #1 (LANS) 4105-45, OP 1 HR, 1380' GIP, R 20' GCM + 180
 O & GCM (NO WTR) NO ISIP, FP'S 13#-72#, FSIP N.A.
 DST #2 (LANS) 4145-4200, OP 30", R 200' O & GCM + 360' O &
 GCSW + 420 GCSW, NO ISIP, FP'S 165#-503#, FSIP 1066#/30"
 RTD 4830', LOG, 4½" @4296' W/175 SX.,
 CO 4250, GRN LOG, PF 40/4128-38 (LAN "A"), § 6 BW W/
 SLI SHO OIL/7½ HRS, 500A (15%), § LD, § 10 BO, GR 36.7 +
 92 BW/NT, § 8 1/3 BF/2 HRS (10% OIL), GAS GA 50,000 CFGPD,
 § 8 BO + 57 BW/6 HRS, TRACER SURVEY, FLUID GOING DOWN TO 4190,
 SQ 4128-38 W/125 SX., CO 4254, PF 8/4150-52 (LAN), § DN, §
 175 GW, NSO/GAS/NT, SQ PERFS 4150-52 (LAN) W/75 SX., CO 4145,

Data Inc

SEWARD CITIES SERVICE OIL
 6-31S-33W #1 GUNN 'B'
 C NW NE

PF 24/4128-34 (LAN "A"), § DN, NO SHO, 500A, § 28 BNO + 47
 BW/7 HRS, GR 35.8 + EST 50,000 CFG, § 60 BO + 71 BW/22 HRS
 GR 36.1 + 80,000 CFG, RAN 2 3/8" TBG TO 4144, § 65 BO + 76
 BWP, GR 36.1 + 80,000 CFG
 POP - PRESS ON DST #1 NOT AVAIL -
 STATE POT: P 39 BOPD + 40%WTR (GR 40.2 DEG) LAN 4128-34
 COMPLETED 9-27-66

MISCEL DATA	GEOL	<u>NOT AVAIL</u>	ELEV	<u>2947 DF</u>	SPUD DATE	<u>7-9-66</u>
	FTG			<u>2939 GR</u>	DRLG COMP	
	SUPPT				FR by DATA	<u>7-7-66</u>
	CSG	<u>8" 612/350 SX</u>	<u>4½" 4296/175 SX</u>		COMP by "	<u>9-29-66</u>