

9-31-34W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg, Wichita, Kansas

Company - WOOD RIVER OIL & REFG. CO., INC.  
Farm - Myers No. 1

SEC. 9 T. 31 R. 34 W  
SEc NW

Total Depth. 2651'  
Comm. 2-21-46 Comp. 4-5-46  
Shot or Treated.  
Contractor.  
Issued. 8-10-46

County. Seward  
KANSAS



Elevation. 2837 ft

Production. 7,000,000 Gas.

CASING:

10" 487'  
7" 2455'

Figures Indicate Bottom of Formations.

sand	140
sand & gravel	175
sand & shells	382
sand & clay	450
red bed	495
red bed & sand	737
red bed	1020
red bed & anhydrite	1110
red bed & shale	1500
lime	1555
anhydrite	1725
lime	1840
lime & shale	1990
red bed	2010
lime & shale	2175
lime	2259
anhydrite	2415
lime	2651
Total Depth.	

Tops:	
Herrington	2436
Krider	2488
Winfield	2545
Ft. Riley	2602