

7 - 31 - 34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. MOBIL OIL COMPANY
Farm. Marguerite Rooney No. 1
Unit

SEC. 7 T. 31 R. 34W
C SW NW

Total Depth. 5680'
Comm. 12-20-61 Comp. 1-16-62
Shot or Treated.
Contractor. Gabbert-Jones Drilg. Co.
Issued. 6-9-62

County Seward
KANSAS



CASING:

8 5/8" 650' cem w/550 sx.
5 1/2" 5380' cem w/200 sx.

Elevation. 2955' DR

Production. 195 BOPD

Figures indicate Bottom of Formations.

surface clay & sand	390
shale & red bed	651
red bed	830
red bed, shale & shells	1230
sand	1435
shale & shells	2250
shale & lime	2360
lime	2941
lime & shale	3049
lime	3137
lime & shale	3375
lime	3442
lime & shale	3715
chalky lime	3831
lime	3965
chalk & lime	4045
lime	4660
lime & shale	4881
lime	5041
shale & lime	5200
lime	5251
lime & shale	5533
shale & sand	5572
sandy lime	5603
shale & lime	5680
Total Depth	

TOPS: SCOUT

Heebner	4048
Lansing	4129
Kansas City	4397
Marmaton	4802
Cherokee	4962
Morrow	5294
Morrow Sand	5316
Chester	5516
St. Genevieve	5608
St. Louis	5626