



Natural Gas • Crude Oil
Exploration & Production

McCOY PETROLEUM CORPORATION

110 South Main, Suite 500
Wichita, Kansas 67202

316-265-9697

Computer Inventoried

McCoy Petroleum Corporation
Rooney "C" #2-18
E/2 NE NW Section 18-31S-34W
Seward County, Kansas

Page 2 ACO-1

DST #1 4739-4775' (Marmaton "A")
Open 30", S.I. 60", Open 60", S.I. 90"
Strong blow. Gas to the surface in 2 minutes.
Gauge 56,800 CFGPD in 20" on 1st open,
" 53,300 CFGPD in 30" "
Gauge 37,400 CFGPD in 10" "
" 36,100 CFGPD in 20" "
" 22,900 CFGPD in 30" "
" 36,100 CFGPD in 40" "
" 20,000 CFGPD in 50" "
" 40,000 CFGPD in 60" "
Recovered 1740' of gassy oil, (reverse out)
70' of oil and gas cut mud,
20' of oil and gas cut watery mud.
FP 131-170# 238-408#
ISIP 1194# FSIP 1173#

DST #2 4783-4819' (Marmaton "B")
Open 30", S.I. 60", Open 60", S.I. 90"
Weak blow throughout both open periods.
Recovered 30' of mud,
180' of water.
FP 57-74# 95-131#
ISIP 1351# 1330#

DST #3 5522-5575' (Chester Sand)
Open 30", S.I. 60", Open 60", S.I. 90"
Gas to the surface in 6 minutes.
Gauge 94,500 CFGPD in 10" on 1st open.
" 116,000 CFGPD in 20" "
" 121,000 CFGPD in 30" "
Gauge 141,000 CFGPD in 10" on 2nd open.
" 141,000 CFGPD in 20" "
" 134,000 CFGPD in 30" "
" 134,000 CFGPD in 40" "
" 134,000 CFGPD in 50" "
" 134,000 CFGPD in 60" "
Recovered 110' of gas cut mud.
FP 78-63# 68-57#
ISIP 1571# FSIP 1550#

COPY

18-31-34W

John Roger McCoy
President

Kevin McCoy
Vice-President

Harvey H. McCoy
Vice-President

Keith McCoy
Treasurer

ELECTRIC LOG TOPS

Winfield	2618 (+ 315)
Council Grove	2836 (+ 97)
Wabaunsee	3210 (- 277)
Heebner	4030 (-1097)
Lansing	4108 (-1175)
Lansing "A"	4146 (-1213)
Marmaton "A"	4760 (-1827)
Marmaton "B"	4795 (-1862)
Cherokee	4938 (-2005)
Atoka	5198 (-2265)
Morrow Shale	5275 (-2342)
Chester Marker	5461 (-2528)
Chester Sand	5550 (-2617)
St. Genevieve	5576 (-2643)
St. Louis	5622 (-2689)
St. Louis "D"	5726 (-2793)
LTD	5825 (-2893)

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1993

CONSERVATION DIVISION
Wichita, Kansas