


1-31-34W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company **GILLES SERVICE OIL COMPANY**
Farm - Sneed No. 1

SEC. 1 T. 31 R. 34W
NE NE SW
100' So. & 100' W/
of den

County. Seward
KANSAS



Elevation. 2940 Ind

Production. 24,700,000 gas
RP 425.9 lb

Total Depth. 2796 = 2791 corr to ground
Comm. 7-6-48 Comp. 7-14-48
Shot or Treated. 37,506 gal
Contractor. Corbett-Barbour Drilling Company
Issued. 12-25-48

CASING:

8 5/8" 640 cem 300 sx
5 1/2" 2795 cem 900 sx
5 1/2" 2790 corr to ground

Figures Indicate Bottom of Formations.

sand clay 350
sand shells 550
red bed 1060
shale shells 1480
sand 1515
shale 1730
shale lime 1785
shale 2000
shale lime 2220
shale 2360
shale lime 2590
lime shale 2675
shale lime 2745
lime 2796

Total depth
2796 = 2791 corr to
ground

TOPS

Herington 2582
Upper Krider 2610
Lower Krider 2636
Winfield 2684
Upper Fort. Riley 2738

perf. 200 shots 2730-2770

8-2-48 2,000 gal 15% acid
2730-2770

8-3-48 9,000 gal 15% acid
2730-2770

6,540 MCF gas 2730-2770

perf 120 shots 2684-2708

" 150 shots 2642-2672

" 50 shots 2622-2632

8-7-48 2,000 gal 15% acid
2622-2672

1,500 gal 15% acid
2684-2708
8-8-48 13,500 gal 15% acid
2622-2672
6,500 gal 15% acid
2684-2708
8-10-48 9,000 gal 5% acid
to all zones
Schlumberger electric log