

3-81-34W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Baughman "D" No. 1

SEC. 3 T. 31 R. 34W
NW NW SE
100' S & 100' E of Center
of the SE/4
County. Seward

Total Depth. 2777'
Comm. 9-27-47 Comp. 10-5-47
Shot or Treated. Acid w/30,000 gals.
Contractor. Corbett-Barbour Drilling Company
issued. 2-28-48

KANSAS



Elevation. 2922' *2nd*
20 Min. Open Flow:
Production. 28,500,000 gas

Figures Indicate Bottom of Formations.

clay & sand	255
sand	470
shale & sand	540
red bed	605
red rock & shale	1100
salt, shale & red rock	1310
red bed & shale	1675
lime	1855
lime & shale	1970
shale & red bed	2110
shale & lime	2235
lime	2305
shale & lime	2385
lime	2777
Total Depth.	

TOPS:

Herington	2526
Upper Krider	2552
Lower Krider	2580
Winfield	2628
Upper Fort Riley	2656
Lower Fort Riley	2734

Perforating Record

180 shots	2686-2722,	4,090 MCF gas
105 "	2634-55,	4,290 MCF gas
170 "	2582-2614,	No increase.
50 "	2552-62,	No increase.

Acidizing Record

11-8-47	4500 gals.	15%	2582-2655
"	2500 gals.	15%	2686-2722
11-9-47	5000 gals.	15%	2686-2722
"	15000 gals.	15%	2552-2655
11-11-47,	9000 gals.	5%	to all zones