

10 - 31 - 34W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Stanley "B" No. 1

SEC. 10 T. 31 R. 34W
SW SW NE
100' N & 100' E of Center

Total Depth. 2820'
Comm. 10-7-47 Comp. 10-14-47
Shor or Treated. Acid.
Contractor. Corbett-Barbour Drilling Co.
Issued. 3-13-48

County. Seward
KANSAS



Elevation. 2935 *ft*

CASING:

8-5/8" 600' Cem. w/325 sx
5-1/2" 2819' Cem. w/900 sx

Production. 20 Min. Open Flow
7,300,000 Gas

Figures Indicate Bottom of Formations.

surface sand & clay	0-190
clay & sand	540
red rock	605
red bed & shale	890
red rock & anhydrite	1125
red rock & shale	1695
lime & shale	1830
shale & lime brks	2000
lime & shale	2400
lime	2820
Total Depth	

Tops:	
Herington	2561
Upper Krider	2586
Lower Krider	2616
Winfield	2662
Upper Fort Riley	2712
Lower Fort Riley	2768

Perforating Record:

130 shots 2712-2738
110 shots 2664-2686
170 shots 2612-2646
50 shots 2584-2594
50 shots 2562-2572

Acidizing Record:

11-19-47 2000 gals. 15% 2712-2738
11-20-47 6000 gals. 15% 2712-2738
11-23-47 1300 gals. 15% 2562-2594
" 2200 gals. 15% 2612-2646
" 1500 gals. 15% 2664-2686
11-24-47 8500 gals. 15% 2562-2646
" 5500 gals. 15% 2664-2686
11-26-47 9000 gals. 5% to all zones.

Shut-in pressure 410.4#.