


HELMERICH & PAYNE., INC.  
 Hyde No. 1.

SEC. 14 T. 31 R. 34W.  
 Center SW  $\frac{1}{4}$

Total Depth. 2850  
 Comm. 11-10-36 Comp. 2-28-37  
 Shot or Treated.  
 Contractor.  
 Issued. 3-13-37

County Seward

MAR 13 1937



CASING.

53/16" 2610'

Elevation.

Production.  $\frac{1}{2}$  M. Gas.

Figures Indicate Bottom of Formations.

surface clay	110
sand	545
sand hard	550
red bed	790
red bed and anhydrite	1010
red bed and lime shells	1140
red bed	1260
red sand	1460
red bed	1480
red bed and shells	1645
red bed	1705
lime	1785
red bed and lime	1850
lime and shale	1920
shale and shells	1985
red bed	2045
red bed, shells and shale	2185
shale and gyp	2300
shale	2304
lime	2395
red rock	2420
shale sticky	2445
red bed	2470
anhydrite	2480
anhydrite and red rock	2515
red bed and anhydrite	2550
anhydrite	2610
red bed and anhydrite	2640
chert and anhydrite	2655
red rock and anhydrite	2690
red bed and shale	2720
red rock and anhydrite	2740
red shale and anhydrite	2790
shale red bed and anhydrite	2840
anhydrite	2850
1/2 million feet gas.	
Total Depth.	