

31-31-34W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. NORTHERN NATURAL GAS PRODUCING CO.
Farm- Stephens "A" No. 1

SEC. 31 T. 31 R. 34W
CE/2 E/2 NW
100' E of C/ N/2

Total Depth. 2765
Comm. 4-14-56 Comp. 4-18-56
Shot or Treated.
Contractor. Michaelis Drilg Co.
Issued. 7-21-56

County Seward
KANSAS



CASING:

8 5/8" 549' cem w/300 sx.
5 1/2" 2758' cem w/800 sx.

Elevation. 2961 R.B.

Production. 10,237,000 CFG

Figures indicate Bottom of Formations.

clay	45
sand, gravel	52
clay	130
sand, gravel	135
clay	170
sand	372
clay	374
sand clay	494
clay, sandstone	535
red bed	1310
sand	1420
red bed, gyp	1790
red bed, anhydrite	2305
anhyd. , shale	2675
shale, lime RTD	2765
Total Depth	

Tops Scout.	
Herington	2610
Lower Krider	2668
Winfield	2710
Upper Ft. Riley	2762