


4-101W +
 MAP NO. _____ SEC. 6 TWP. 31S RGE. 34W
 STATE Kans. COUNTY Seward 150' East of loc. C SW NW
 OPERATOR Socony Mobil Oil Co. FT. FROM _____ LINE _____
 WELL NO. 4 FARM NAME George B. Strong Unit FT. FROM _____ LINE _____
 Cutter ELEV. 2906 GR 2914 DF 2917 KB
 1/15/62 SPUD 1/15/62 COMP. 4/17/62

CONTR. Gabbert-Jones Drlg. rig #2 /GEOL.
 COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
Morrow	5290-5291	8	Nat
Chest	5540-84	76	Nat

 Co. Test (Morr)
 I. P. OIL/DIST. Fl 248 BQTR. 5 BW GAS 542 M.C.F.P.D. 24/64" CHK Gr 41.9° HRS. 24
 Co. Ist (Chest) Fl. 114 BO +3 BW, 106 " 18/64" " Gr 42.4° 24
 " " (Dual Completion) " " "



D & A ()
 SIP# GOR 935 (Chest) TP # _____ FI CPH _____ SIBHP _____
 GOR. 2188 (Morr) GR. _____ PBDT 5612 TD 5665

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
8-5/8"	617	500			
5 1/2"	5640	1250			

OPERATOR Socony Mobil Oil Co. WELL NO. 4 Geo. B. Strong Unit ELEV. 2914 DE

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
DF Tops & Datums					
Lans	4054		Hb	3995	-1081
Kc	4337		Lans	4072	-1155
Marm	4705		Kc	4354	-1440
Cher	4909		Marm	4727	-1813
Morr	5246		Cher	4924	-2010
RTD (Chest) 5665			Morr	5261	-2347
			Morr sd	5290	-2376
RTD 5665 (Chest) No DST's			Chest Marker	5510	-2596
Log, 5 1/2" @ 5640 w/1250 sx,			Chest Sd	5540	-2626
CO 5612 PBDT, 32/5576-84			LTD (Chest) Not available		
(Chest) Swb dry, NS, 44/5540-62					
(Chest) \$ 3 BF/17 hrs, Est. 90% wtr, Fl 213 BLO/16 hrs,					
22/64" ck, \$ & Fl 1d, Fl 179 BNO/24 hrs, TP 385#, Fl 257					
BNO/NW/24 hrs, TP 412#, Ga 180 Mcfgpd, Fl 8 BNO/1 hr					
Gr 42.8 deg., GOR 700-1, Pkr @ 5435 1d w/25 BLO, 8/5290-91					
(Morr) ran tbg w/pkr @ 5243, \$ 15 BLO + 27 BNO/10 hrs,					
w/GSG/NW, \$ & Fl 24 BNO/8 hrs, Set pkr @ 5333, \$ 10 BLO +					
14 BNO/3 hrs from 5000' kick-off & fl 14 BNO/2 hrs, TP 20#,					
Fl 18 BNO/4 hrs, TP 20#, Fl 4 BNOPH/NW/last hr., TP 30#.					

SITP 130/45, flo 90 BNO/24 hrs, g 621 MCF, TP 0-20,
 GOR 690:1, Chest 5540-84, swb & flo 73 BNO/NW/24 hrs,
 TP 0-20, SITP 120/1 hr, SITP 150/2 hrs, Morr 5290-91,
 2½" tbg to 5477 thru pkr @ 5333, 2½" tbg to 5192,
 Co Tst, flo 248 BO + 5 BXW/24 hrs, 24/64" ck, TP 280,
 g 542 MCF, GOR-1, Gr. 41.9°, Morr 5290-91,
 Co. Fl 114 BO + 3 BXW/24 hrs, 18/64" ck, TP 320#,
 G 106 MCF, GOR 935:1, G. 42.4°, Chester 5540-84.

LIBERAL ELECTRIC LOG TOPS

2917 KB

Winfield 2592 (+325)
 Council Grove 2816 (+101)
 Heebner 3998 (-1081)
 Toronto 4018 (-1101)
 Lansing 4114 (-1197)
 Marmaton 4746 (-1809)
 Morrow 5264 (-2347)
 "S2" Sand 5290 (-2373) 24/24; NT; flo 248 BOPD + 5 BW + 542 MCF
 Chester 5482 (-2565)
 Sand 5540 (-2623) 0/36; φ flo 114 BOPD + 3 BW + 106 MCF
 Ste. Gen 5604 (-2687)
 TD 5665