

18 - 31 - 35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - MAGNOLIA PETRO. CO.
Farm - Hinshaw Estate No. 1

SEC. 18 T. 31 R. 35W
NW NW SE

Total Depth. 2788' K.B.
Comm. 7-3-48 Comp. 7-11-48
Shot or Treated. Acidized
Contractor. Holm-Louis Drlg. Co.
Issued. 10-23-48

County. Stevens
KANSAS



Elevation. 3011' Sand.

Production. 20,450,000 gas

CASING:

10 3/4" 648' cem w/400 sx.
7" 2787' cem w/1000 sx.

Figures indicate Bottom of Formations.

clay and shells	45
clay, sand & shells	110
sand, gravel & shale	465
shale and shells	565
red bed	648
red	1080
anhydrite	1155
redbed & gypsum	
shells	1315
redbed and shale	1610
shale and shells	1690
lime and shale	2595
lime	2665
lime and shale	2788
total depth	K.B.

Tops:
Towanda 2704' K.B.

Ran H. Liburton electric log.

Perf. 2700-36 w/168 sh.,
acidized w/7000 gals acid.
Perf. 2650-70 w/96 sh.,
acidized w/7000 gals acid.
Perf. 2596-2628 w/144 sh.,
acidized w/7000 gals acid.