

15-31-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - MAGNOLIA PETRO. CO.
Farm - E. L. Gaskill No. 1

SEC. 15 T. 31 R. 35W
NW NW SE

Total Depth. 2861' K.B.
Comm. 7-4-48 Comp. 7-15-48
Shot or Treated. Acidized
Contractor. Keating Drlg. Co.
Issued. 10-23-48

County. Stevens
KANSAS



CASING:

10 3/4" 673' cem w/400 sx.
7" 2860' cem w/1000 sx.

Elevation. 3002 Ind.

Production. 8,256,000 gas

Figures Indicate Bottom of Formations.

sand and clay	450
clay and gravel	570
red bed	590
sand	640
redbed and sand	785
shale sdy	1260
sand and shale	1765
shale sdy	1780
shale and anhydrite	2055
anhydrite	2120
shale sdy	2285
shale & anhydrite	2375
anhydrite	2420
lime and anhydrite	2475
lime	2525
lime and chert	2555
anhydrite and lime	2590
shale and lime	2600
anhydrite	2625
anhydrite and lime	2660
lime	2680
lime and shale	2840
shale	2861
total depth	K.B.

Tops:

Towanda 2778' K.B.

Ran Halliburton electric log.

Perf. 2778-2810 w/144 sh.,
acid zed w/7000 gals acid.
Perf. 2724-46 w/96 sh.,
acidized w/7000 gals acid.
Perf. 2677-2704 w/120 sh.,
acidized w/17000 gals. acid.
Perf. 2642-56 w/72 sh.,
acidized w/7000 gals acid.