

4-31-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - MAGNOLIA PETRO. CO.
Farm - O'Dea Estate No. 1

SEC. 4 T. 31 R. 35W
NW NW SE

Total Depth. 2760' K.B.
Comm. 8-26-48 Comp. 9-7-48
Shot or Treated. Acidized
Contractor. Corbett-Barbour Drlg. Co.
Issued. 10-23-48

County. Stevens
KANSAS



Elevation. 2946 Ind.

Production. 16,300,000 gas.

CASING:

10 3/4" 603' cem w/400 sx.
7" 2756' cem w/1000 sx.

Figures Indicate Bottom of Formations.

sand	40
sand and shale	300
shale and shells	565
red bed	603
red bed	615
redbed and shale	1065
redbed and shells	1200
sand and shells	1520
redbed and shale	1685
sand and shale	1935
lime brkn	2085
lime and shale	2180
lime and gypsum	2250
lime brkn	2305
shale and lime	2335
lime and gypsum	2375
lime chalky	2445
gyp and lime	2480
lime	2760
total depth	K.B.

Tops:

Towanda 2659' K.B.

Ran Halliburton electric log

Perf. 2660-2700 w/192 sh.
acidized w/7000 gals.
Perf. 2413-31 w/96 sh.,
acidized w/7000 gals.
Perf. 2564-94 w/144 sh.,
acidized w/7000 gals.