

State

Kansas

County

Comanche

Company Messman-Rinehart Oil Co.Well No. 1Farm Schuette Estate "B"

Survey

Block No. 36 Sec. 31 Twp. S Range 16 W


Co-Ord.

Elev.

2001 K/B
1998 D/F

C. S/2 SE/4

M-R Rig



50% - A. A. Seeligson, Jr.

25% - Chicago Group

12.5% - Roger L. Messman

12.5% - C. B. Rinehart

ORI - Pan American, Liberal
John W. Mason, Geo

4900' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 660

Ft. from S. Line

Ft. from W. Line 1320

Ft. from E. Line

Date	Depth	
11/30/60		Location staked
12/5		M.I.R.T. - Spud - 10-3/4" @ 254' w/200 sx. cem. 4 c.c., P.D. @ 1:50 a.m. 12/6/60
12/7	950	Drlg.
12/8	2100	Drlg.
12/9	2540	Drlg. (#2 @ 2225) (#3 @ 2441)
12/12	3600	Drlg. (#6 @ 3440) (visc. 42, water loss 15, wt. 10.3)

Date	Depth	690793
12/13	3885	Drlg. (#7 @ 3670)
12/14	4130	Drlg. (#8 @ 3945)
		(vic. 42, wtr. loss 12.8, wt. 10#)
12/15	4321	Drlg. (#9 @ 4175) lost circ.
	4120	Heebner (-2119)
	4284	Lansing (-2283)
12/16	4460	Drlg. (regained circ.)
		(visc. 55, wtr. loss 14)
12/17	4600	Drlg. (#11 @ 4507)
		(#12 @ 4630)
12/18	4707	Drlg. (#13 @ 4707)
12/19	4840	Drlg. (Miss. esti. 4844)
	4849	Miss. (-2848)
12/20	4907	Drlg.
		D.S.T. #1 - 4846-84' - Op. 1 hr., Rec. 20'
		mud, BHP 145-175#, FP 35-45#
		Hhd. 2655-2575#
	4958	Miss. Lm. (-2957)
12/21	4980	Drlg.
		D.S.T. #2 - 4887-4947 - Op 44", wk. bl.
		Rec. 60' mud w/spots of oil,
		BHP 1090-325#, FP 45-65#
	4990	R.T.D. (Sj. Log)
		D & A - 12/22/60