


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

PANHANDLE EASTERN PIPE LINE &
SATURN OIL & GAS CO.
Parsons No. 1.

SEC. 3 T. 31 R. 37W
Cen NW $\frac{1}{4}$

Total Depth. 2796'
Comm. 10-1-37 Comp. 11-5-37
Shot or Treated. 1000 & 3000 Gals.
Contractor. F. Murphy
Issued. 4-2-38

County. Stevens



Rotary 2406'

CASING:

10 $\frac{3}{4}$ " 603'
7 " 2400'

Elevation.

Production. 7,219,000 G.
R.P. 426#

Figures Indicate Bottom of Formations.

gravel	170	Gas log
sand	450	sh gas 2470
gravel	510	sh gas 2495-2500
clay yellow	525	open flow 2510-2515 3,075,000 cu ft
red rock & clay	980	10-29-37 well blew down to 2,700,000 cu ft @ 2600
red rock & gyp	1140	sh gas - open flow 3,000,000 cu ft 2610
red rock	1230	increase open flow 3,211,000 cu ft 2687-2698
sand	1240	open flow taken 11-3-37 well shut down in 17 hrs
red rock	1430	3,587,000 cu ft
red rock, sand & shale	1640	
gyp	1660	Acidized
red rock & gyp	1875	Open flow 11-7-37 7,219,000 cu ft
gyp	1945	
red rock & gyp	2050	
gyp & anhydrite	2160	
gyp & brkn lime	2225	
anhydrite	2325	
anhydrite & gyp	2406	
lime	2415	
shale blue	2445	
sh gas 2470		
sh gas 2495-2500		
sh gas 2510-15		
brkn lime	2515	
red rock	2530	
lime hrd	2570	
lime brkn	2575	
red rock	2595	
brkn lime	2605	
grey lime	2687	
lime sdy	2698	
brkn lime	2715	
lime grey	2725	
red rock	2740	
sdv lime	2796	
Total Depth.		