

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

PANHANDLE EASTERN PIPELINE CO.
Newby No. 1.


SEC. 27 T. 31 R. 37W.
Center NW $\frac{1}{4}$

Total Depth. 2850 P.B. 2650
Comm. 1-3-38 Comp. 1-31-38
Shot or Treated.
Contractor.
Issued. 5-21-38

County Stevens.

CASING. Hole drilled to 2489 with
Rotary.

7" 2481'



Elevation.

Production. 3,500,000G.

Figures Indicate Bottom of Formations.

broken lime and anhyd	2489-	2509
lime grey	2520	
broken shale	2525	
broken lime	2542	
lime grey	2550	
shale blue	2555	
lime grey	2575	
broken lime	2595	
sdv lime	2600	
lime grey	2620	
red rock	2628	
lime sholl	2630	
shale grey	2645	
lime grey	2650	
broken lime	2660	
red rock	2665	
broken lime	2680	
red rock	2685	
sdv lime	2697	
lime grey	2754	
shale blue	2760	
sdv lime	2800	
red rock	2814	
shale white	2820	
broken lime	2845	
red rock	2850	
Total Depth.		

GAS LOG.

2570-2575	show of gas	open flow	250,000 cu ft.
2595-2600	show of gas	Open flow	500,000 cu ft.
2628-2630	show of gas	open flow	1,853,000 cu ft.

O.F. taken Feb 6 after being shut in 5 days	2,173,000 Gas.
O.F. After acidizing with 2000 gal	1,495,000 gas
O.F. After acidizing with 5000 gal	3,500,000 Gas

Plugged back to 2650