

19-31-37W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY HUGOTON PRODUCTION CO.

SEC. 19 T. 31 R. 37W

FARM Fulk


NO. 1

LOC. SE SE NW

2347' S. of N.L. & 2350' E. of
W.L.

COUNTY Stevens

KANSAS



TOTAL DEPTH 2691'

COMM. 12-22-50

COMP. 1-7-51

SHOT OR TREATED

CONTRACTOR Walter Kuhn Drilling Co.

ISSUED 3-3-51

CASING

10 3/4" 538' cem. w/325 sx circulated
 7" 2443' cem. w/800 sx circulated
 5 1/2" 157'6" liner

ELEVATION 3133 Ind.
3125 ground

PRODUCTION 7,448,700 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay	60
clay	150
sand & clay	500
red bed	520
cement	545
red rock	625
red bed gyp	900
sandy red bed	1050
anhydrite	1145
red bed	1175
red rock & shale	1300
red sand	1400
shale & red rock	1438
red bed & anhydrite	1800
shale & lime	1835
lime	1900
anhydrite shale	2030
lime & shale	2130
lime	2460 RTD

CABLE TOOLS

lime	2528
shale	2548
lime	2691

Total Depth

Tops:

Hollenberg	2402
Herrington	2447
Krider	2466-2525
Winfield	2541-2581
Upper Ft. Riley	2598-2648
Lower Ft. Riley	2652

Gas Log

2514	3800.0
2525	5285.5

2536	5074.2
2560	5074.2
2580	5074.2
2620	5371.0
2650	5074.2
2685	5488.3