

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company: REPUBLIC NATURAL GAS COMPANY
Farm W. R. Kenoyer No. 1

SEC. 24 T. 31 R. 37W
NE NE SW
100' S & 100' W of Cen Sec.

Total Depth. 2767'
Comm. 9-15-47 Comp. 10-5-47
Shot or Treated. Acidized
Contractor. Gabbert & Lindas Drlg. Co.
issued. 5-15-48

County. Stevens

KANSAS



Elevation. 3089 *nh*

CASING:
10-3/4" OD 542' Cem. W/250 Sx.
7" OD 2541' Cem. W/800 Sx.
5 1/2" OD liner 236'

Production. 20 min. open flow
25,241,000 Gas 72 hr test

Figures indicate Bottom of Formations.

sand & shale	150
sand	515
red rock	554
red bed & sand	1105
shale, shells & sand	1640
shale & shells	2045
lime & shale	2145
Formation not logged	2315
shale & shells	2410
lime & shale	2550
conglomerate	2560
lime	2575
shale blue	2577
formation not logged	2593
lime	2635
lime broken	2665
lime	2670
red rock (cavy)	2680
lime	2763
sand lime	2767
Total Depth	

Tops:	
Sandy Herington	2533
Xyln. Herington	2540
Base Herington	2550
Krider	2593
Winfield	2635
Fort Riley	2680

"	2697-2720	1,705 MCF
"	2720-2729	1,884 MCF
"	2729-2751	1,992 MCF
"	2751-2767	1,992 MCF

Well was treated Oct. 19, 21, & 23, 1947
with 17,700 gals. of 15% acid & 6,000 gals.
of 5% acid. Well gauged 25,241,000 DF after
acid on 20 mins. open flow, 72 hr shut in.

Gas Log:		
First Gas	2577	Show
Increase Gas	2648	-
"	2655	-
"	2655-2680	-
"	2680-2686	-
"	2686-2697	1,501 MCF

