


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg, Wichita, Kansas

Company - REPUBLIC NATURAL GAS COMPANY
Farm - Brewer No. 1

SEC. 26 T. 31 R. 37W
NE NE SW
100' S & 100' W of Cen
of the sec.
County. Stevens
KANSAS

Total Depth. 2769'
Comm. 8-22-47 Comp. 9-30-47
Shot or Treated.
Contractor. Gabbert & Lindas Drilling Co.
Issued. 1-24-48



CASING:
5 1/2" 2535'

Elevation. 3087 ft.

Production. 31,968,000 gas open
flow.

Figures Indicate Bottom of Formations.

Surface	40
sand & shells	530
red rock	580
redbed, sand & shells	1140
shale	1560
shale, lime & shells	1705
shale & shells	2040
lime & shale	2110
shale & shells	2350
lime & shale	2576
lime	2615
blue shale	2620
red rock	2625
lime	2668
red rock	2675
lime	2769
Total Depth.	

FORMATION TOPS:

Herington	2542-2555
Krider	2584-2615
Winfield	2625-2663
St. Riley	2675

GAS LOG:

first gas	2576	show
increase gas	2600	457 MCF
" "	2600-2635	792 "
" "	2635-2640	1,022 "
" "	2640-2656	1,210 "
" "	2656-2663	1,372 "
" "	2663-2680	1,446 "
" "	2680-2695	2,743 "
" "	2695-2700	2,663 "
" "	2700-2720	2,705 "
" "	2720-2728	2,780 "

Well was treated Oct. 16th, 18th, and 20th, 1947 with 18,500 gallons of 15% and 4,500 gallons of 5% acid. Well gauged 31,968 MCF after acid on 20 minute open flow 72, hour shut in.