


29-31-37W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HUGOTON PRODUCTION CO.  
Farm- Grubbs No. 2

SEC. 29 T. 31 R. 37W  
C NW NW

Total Depth. 6005' PB 3010'  
Comm. 10-14-58 Comp. 11-8-58  
Shot or Treated.  
Contractor. Garvey Drlg.  
Issued. 1-24-59

County Stevens  
KANSAS  


CASING:  
13 3/8" 568' cem w/550 sx.  
8 5/8" 3060' cem w/600 sx.

Elevation. 3138' KB  
Production. 7,500,000 CFG

Figures Indicate Bottom of Formations.

rock, clay & sand	295
gravel & sand	515
red bed	1085
gyp & red shale	1190
shale & shells	1522
sand, shale & shells	1795
gyp & shale	2075
shale & Anhydrite	2178
lime & shale	2499
lime	3855
lime & shale	3959
lime	4295
chalky lime	4410
lime	4768
lime & chert	4835
lime	4975
lime & shale	5065
lime	5150
lime & shale	5366
shale	5690
shale & lime	5776
lime	6005

Total Depth  
Plugged back to 3010' and is to be tested in the Council Grove formations.

TOPS:

Hollenberg	2437
Herrington	2486
Upper Krider	2502
Lower Krider	2526
Winfield	2580
Upper Fort Riley	2643
Lower Fort Riley	2698
Wreford	2786
Council Grove	2822
Admire	3078
Wabaunsee	3234
Cherokee	3585

Heebner	4020
Toronto	4056
Lansing-Kansas City	4121
Marmaton	4838
Cherokee	4983
Atoka	5274
Morrow	5428
Chester	5761
St. Genevieve	5975