

30-31-37W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY HUGOTON PRODUCTION CO.

SEC. 30 T. 31 R. 37W

FARM Musgrove


NO. 1

LOC. NE NE SW
2780' WEL, 2445' NSL of SW/4

Stevens

COUNTY

KANSAS



TOTAL DEPTH

2720

COMM.

9-2-50

COMP. 9-24-50

SHOT OR TREATED

CONTRACTOR

Walter Kuhn Drlg. Co.

ISSUED

12-2-50

CASING

10 3/4" 566' cem w/325 sx.

1" D 2470' cem w/800 sx.

5 1/2" liner 259'

ELEVATION

3135' and
3149.0'

PRODUCTION

34,899,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sandy clay	110
sand, gravel	375
clay, sand	500
red bed	575
redbed	660
redbed, gypsum	780
redbed, shale	1100
anhydrite	1250
redbed sdy	1685
anhyd.	1800
lime, shale	1895
anhyd.	2135
lime, shale	2240
anhyd.	2300
anhyd., shale	2360
lime, shale RTD	2487
le	2494
lime	2557
shale	2577
lime	2610
shale	2630
e	2720
Total Depth	

Tops:

Hollenberg	2433	--
Herrington	2475	--
Krider	2494	- 2553
Winfield	2570	- 2609
Upper Ft. Riley	2631	- 2677
Lower Ft. Riley	2683	

2555	5204.4
2580	9362.6
2580-90	inc.
2595	9671.0
2620	9671.0
2630	10393.5
2656	8365.5
2675	8365.5
2700	8188.1
2712	8188.1
2720	8188.1

GAS LOG

gas log	MCF
2496-2505	show
2525	1465.7
2525-55	inc.
2535 (2535)	4643.8