


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. HUGOTON PROD. CO.
Farm. Allen No. 1

SEC. 2 T. 31 R. 37W
NE NE SW
2788.6' WEL & 2576.3' N SL

County. Stevens
KANSAS

Total Depth. 2724'
Comm. 3-6-49 Comp. 3-28-49
Shot or Treated. Acidized
Contractor. Walter Kuhn Drlg.
Issued. 3-28-49



CASING:
10-3/4" OD 495' Cer. W/300 Sx. Circ.
7" OD 2483' Cem. W/800 Sx. Circ.
5 1/2" Liner 263' 5"

Elevation. 3066' 2nd
Product in 7,026,000 gas
Orig. R.P. 395# SG

Figures Indicate Bottom of Formations.

sand & clay	495
red bed	865
red bed & gyp	1280
red bed	1445
red bed & gyp	1640
anhy. & shale	1820
shale & shells	1917
red rock & anhy.	2040
anhy. & red bed	2120
anhy. & shale	2265
lime, shale & gyp	2350
lime & shale	2460
lime RTD	2485
lime	2546
blue & red shale	2550
lime	2555
shale red	2560
lime & shale	2565
lime	2602
red rock	2623
lime	2680
shale	2683
lime	2724

Total Depth

1st gas 2494 2500 open flow

too small to gauge

ind. 2536 3,029 MCF

inc. 2536 2546 4,538 MCF

Inc. 2546 2567 4,867 M CF

Blew down to 4,770 MCF 2577

Blew down to 4,770 MCF 2585

Blew down to 4,491 MCF 2590

Blew down to 4,491 MCF at 2600

Ind. 2600 2625 4,681 MCF

Blew down to 4,584 MCF 2630

Inc. 2630 2652 4,681 MCF

Ind. 2653 2668 4,867 MCF

Blew down to 4,867 M CF 2678

Blew down to 4,770 MCF at 2688

Inc. 2688 2697 5,032 M CF

Blew down to 2,867 MCF at 2703

Blew down to 4,770 MCF at 2711

Blew down to 4,770 M CF at 2724

Well tested 7,026 MCF on 4-19-49

72 hr shut-in test before acid.

R. P. before acid. 395# SG

Tops:

Hollenberg 2413

Herrington 2459

Krider 2487

Winfield 2558

Upper Ft. Riley 2622

Lower Ft. Riley 2680