

A copy of all wireline logs and drillers time log shall be attached with this form. Submit QP-4 form with plugged wells. Submit CP-111 form with all temporarily abandoned wells.

SIDE TWO

Operator Name Anadarko Petroleum Corp. Lease Name..... Parsons "J" Well #..... 1H

Sec..... 4 Twp..... 31S Rge..... 37 ☐ East ☒ West County..... Stevens

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☐ Log ☒ Sample

Name	Top	Bottom
Sand, Redbed	0'	522
Redbed	522	1229
Glorietta Sand	1229	1390
Redbed	1390	2339
Lime, Shale	2339	2840
TD		2840

CASING RECORD ☒ Now ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24.0	522	Pozmix & Common	350	3% CC
Production	7-7/8"	5-1/2"	14.0	2840	Class C	240	10% DCD, 20% DCD

PERFORATION RECORD

Shots Per Foot Specify Footage of Each Interval Perforated

Acid, Fracture, Shot, Cement Squeeze Record

(Amount and Kind of Material Used) Depth

TUBING RECORD

Size

Set At

Packer at

Liner Run

☐ Yes☐ No

Date of First Production

Producing Method

☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain)...

GABBERT-JONES
DRILLERS WELL LOG

4-31-37W

PARSON "J" 1H
SEC. 4-31S-37W
STEVENS COUNTY, KANSAS

Commenced: 11-22-88
Completed: 11-25-88
Operator: ANADARKO PETROLEUM CORPORATION

Depth		Formation	Remarks
From	To		
0	522	Sand - Redbed	Ran 12 jts of 24# 8 5/8"
522	1229	Redbed	csg LD @ 512' w/200 sks
1229	1390	Glorita Sand	75/25 posmix - 2% CC - 1/4# FS
1390	2339	Redbed	150 sks Common - 3% CC
2339	2840	Lime - Shale	1/4# FS PD @ 10:15 PM 11-22-88.
2840	TD		Ran 71 jts of 14# 5 1/2" csg LD @ 2840' w/200 sks Class C - 20% DCD - 2% CC 1/4# FS - 40 sks Class C 10% DCD - 2% CC - 1/4# FS PD @ 11:00 AM 11-25-88. RR @ 12:00 Noon 11-25-88.

RECEIVED
STATE CORPORATION COMMISSION
1989
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick

) I, the undersigned, being duly sworn on oath, state
) that the above Drillers' Well Log is true and correct
) to the best of my knowledge and belief and according
) to the records of this office.