

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

6-31-37W

Company- B. A. HARDEY
Farm- McClure

No. 2

SEC. 6 T. 31 R. 37W
C SW

Total Depth. 5870'

Comm. 6-5-59


Comp. 7-7-59

County Stevens
KANSAS

Shot or Treated.

Contractor. McKnab & Lindsay

Issued. 9-26-59



CASING:

8 5/8" 1750' cem w/900 sx.

5 1/2" 5449' cem w/250 sx.

DV tool @ 3074' cem. top zones w/250 sx. pozmix.

Elevation. 3112' RB

Production. 8,200,000 CFG

Figures indicate Bottom of Formations.

sand	544
sand & shale	1000
shale & lime	1135
sand & shale	1165
shale & lime	2450
sand & shale	2750
lime & shale	2944
lime	3027
lime & shale	3095
shale	3173
lime & shale	3443
lime	3965
lime & shale	4086
lime	4770
lime & shale	4818
lime	4858
lime & shale	4977
shale	5004
shale & lime	5171
shale	5249
sand & shale	5379
shale	5491
shale & sand	5575
lime & shale	5638
lime	5870
Total Depth	

TOPS: SCOUT

Herington	2422
Council Grove	2745
Wabaunsee	3146
Shawnee	3499
Heebner	3908
Toronto	3944
Lansing	4015
Marmaton	4595
Cherokee	4772
Morrow Shale	5210
Morrow Sand	5316
Chester	5543
St. Gen.	5686
St. Louis	5768