


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HUGOTON PROD. CO.
Farm - Thruow No. 1

SEC. 15 T. 31 R. 37 W
CEN. SEC.
2643.3' SNL in Cen. of Sec.

Total Depth. 2764'
Comm. 3-7-49 Comp. 3-29-49
Shot or Treated.
Contractor. Walter Kuhn Drlg.
Issued. 8-6-49

County. Stevens
KANSAS



CASING:
10-3/4" 522' OD Cem. W/300 Sx. Circ.
7" OD 2498' Cem. W/400 Sx. Circ.
5 1/2" OD liner 281'

Elevation. 3084' *end*

Production. 2,660,000 gas

Figures Indicate Bottom of Formations. Orig. R.P. 429# SG

sand & clay	200
sand & gravel	345
sand & clay	475
clay	485
red bed	533
red bed	750
anhydrite	785
shale & red bed	1140
anhydrite	1260
red bed & salt	1350
red bed	1420
red bed & shale	1740
anhy. & lime	1820
lime & shale	1960
red bed & shale	2100
lime & shale	2315
lime, shale & anhy.	2380
lime RTD	2521
lime	2523
lime & shale blue	2527
lime	2580
shale red	2588
lime	2625
shale red	2650
lime	2764
Total Depth	

Tops:	
Hollenberg	2462
Herrington	2509
Krider	2530
Winfield	2589
Upper Ft. Riley	2646
Lower Ft. Riley	2705

1st gas 2545 Show
Inc. 2555 2565 not tested
Inc. 2590 2605
Inc. 2655 2665
Driller's report for 3-28-49
shows: 1.2" wtr at 10:30 a.m.
equals 1,597 MCF.
Inc. 2675 2700
Inc. 2720 2700 MCF
Blew down to 2660 MC⁺ at 2764'