

4-31-39W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas

Company - ST MOLIND OIL AND GAS CO.  
Farm - Baker GU "B" No. 1

SEC. 4 T. 31 R. 39W

SW 1/4 NE  
2490' S of NL,  
2490' W of EL of NE/4

County. Morton  
KANSAS



Total Depth. 2607'  
Comm. 1-17-48 Comp. 2-20-48  
Shot or Treated. acid  
Contractor.  
Issued. 11-13-48

CASING:

10 3/4" 605' cem w/700 sx.  
6 5/8" 2400' cem w/350 sx.  
5" 2592' Slotted

Elevation. 3194' Ind

Production. 10,120,000 gas

Figures Indicate Bottom of Formations.

|                  |         |
|------------------|---------|
| sand and clay    | 533     |
| red bed          | 612     |
| redbed and sand  | 1526    |
| salt and redbed  | 1769    |
| sand and lime    | 1944    |
| shale and redbed | 2144    |
| shale            | 2214    |
| dolomite & shale | RTD2400 |
| lime and shale   | 2500    |
| lime             | 2585    |
| lime and salt    | 2599    |
| lime             | 2607    |
| total depth      |         |

Ran Schlumberger to 2586'

Tops:

|                  |           |
|------------------|-----------|
| Herington-Krider | 2403-2447 |
| Winfield         | 2464-2497 |
| Towanda          | 2522-2560 |
| Ft. Riley        | 2577-2610 |

Acidification

AW 2000 at 15% displaced.  
Max press 200#. Broke to  
vac. time 13 min.  
REW 17,500 gal., 15%,  
8,190 gal flush, using  
6 pump trucks, max.  
press 300#. Broke to vac.  
time on acid 19 min. on  
water 13 min.