


16-31-39W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL AND GAS COMPANY
Farm - Daniels Gas Unit No. 1

SEC. 16 T. 31 R. 39W
SW 1/4 NE
2540' SNL & 2540' WEL of Sec.

County. Morton
KANSAS



Total Depth. 2596'
Comm. 8-25-47 Comp. 10-7-47
Shot or Treated. Acidized
Contractor.
Issued. 11-14-47

Elevation. 3201 *act*

Production. 20 min. Open Flow:
8,175,000 Gas

CASING:

10-3/4" 644' Com. w/450 sx
7" 2363' Com. w/350 sx

Figures Indicate Bottom of Formations.

sand & clay	0-560
red bed	648
red bed & sand	1177
lime & red bed	1460
sand, shale & lime	1710
lime & shale	1900
lime	1942
lime, shale & anhydrite	2160
lime & shale	2380
lime	2400
red rock & lime	2457
lime & red rock	2526
lime & shale	2596
Total Depth	

Ran Schlumberger to 2588

Acidizing:

Acid. w/2000 gals. 15% acid.

Reacid. w/15,000 gals. 15% acid.

Tops:

Herington-Krider	2372-2416
Winfield	2446-2468
Towanda	2505-2539
Fort Riley	2558