

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


21-31-39W

Company- PAN AMERICAN PETR. CORP.
Farm- Cooper Gas Unit "D" No. 1

SEC. 21 T. 31 R.39W
C NE SW

Total Depth. 6400' PB 3807'
Comm. 2-23-61 Comp. 4-14-61
Shot or Treated.
Contractor. Barbour Drlg.
Issued. 7-22-61

County Morton
KANSAS



CASING:
10 3/4" 703' cem w/500 sx.
4 1/2" 3835' cem w/300 sx.

Elevation. 3228' DF

Production. 600,000 CFG

Figures indicate Bottom of Formations.

surface sand-clay	240
gyp-shale	590
redbed	720
shale	815
redbed-sand	1180
Anhydrite	1271
red shale	1381
sand, shale, chalk	1705
Anhydrite	1725
shale, sand	1817
Anhydrite, shale, sand	1970
lime, shale	2245
Anhydrite	2405
lime, shale	2805
lime	2868
lime, dolomite	2973
lime, shale	3552
lime	3740
lime, shale	3812
lime	4964
lime, shale	5494
shale, pyrite	5559
lime, shale	5906
lime	6400
Total Depth	
Plugged back to 3807'	

TOPS: SCOUT	
Council Grove	2672
Pennsylvania	3102
Missourian	3963
Des Moines	4670
Morrow	5364
Morrow Sand	5716
Chester	5837
St. Genivieve	5900
St. Louis	6016
Salem	6214