

30-31-39W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company • STANOLIND OIL AND GAS COMPANY
Farm • Melburn Gas Unit "A" No. 1

SEC. 30 T. 31 R. 39W
SW SW NE
2490' SN1 & 2490' WE1 NEc

Total Depth. 2570'
Comm. 2-4-48 Comp. 2-29-48
Shot or Treated. Acidized
Contractor.
Issued. 7-31-48

County. Morton
KANSAS



CASING:

10-3/4" 565' Cem. w/400 sx
6-5/8" 2356' Cem. w/750 sx

Elevation. 3233 Ind.

Production. 20 Min. Blow Down:
7,108 cu. ft. Gas

Figures Indicate Bottom of Formations.

clay, sand & red bed	0-575
red bed & sand	992
sand, red bed & gyp	1579
red bed & shells	1947
shale	2110
anhydrite & shale	2206
dolomite & shale	2305
dolomite	2360
lime	2455
shale	2465
red rock & lime	2482
lime	2517
shale	2541
lime	2570
Total Depth	

Acidization

All zones AW 2000 gal 15%,
Displaced. Max press 350#.
Broke to 75#, Time 13 min.
All zones REAW 16,000 gal.
15%, 11,600 gal flush, using
6 pump trucks. Max press 200#.
Broke to 150#. Time on acid 16
min. on flush, 10 min.

Tops:

Herington-Krider	2356-2395
Winfield	2411-2450
Towanda	2473-2512
Ft. Riley	2538-2570