

26-31-4W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

D. R. LAUCK OIL CO., INC. &
Company- PETROLEUM ASSOCIATED FUND, INC.
Farm- Heimerman No. 1

SEC. 26 T. 31 R. 4W
SE SE NE

Total Depth. 4462'
Comm. 11-1-62 Comp. 11-18-62
Shot or Treated.
Contractor. Lauck Drilling
Issued. 2-23-63

County Sumner
KANSAS



CASING:
8 5/8" 227' cem w/160 sx.

Elevation. 1314' DF

Production. DRY

Figures Indicate Bottom of Formations.

red bed & clay	227	DST #2 3495-3516' Op 45 min. w/very
shale	675	weak blow 20 min. Rec. 5' mud w/few
shale & anhydrite	855	specks of oil. ISIP 54#/30 min., FSIP
lime & shale	1395	37#/30 min., IFP 18#, FFP 18#.
shale & lime	1695	
shale & shells	1850	DST #3 3991-4018' Op 1½ hrs. w/weak
shale & lime	2310	steady blow. Rec. 70' oil specked
lime & shale	2580	drilling mud & 60' oil specked watery
shale & lime	2780	drilling mud. ISIP 1513#/30 min., FSIP
lime & shale	3104	1045#/30 min., IFP 16#, FFP 82#.
Stalnaker sand & shale	3150	
lime, shale & sand	3205	DST #4 4449-4456' Op 30 min. w/weak
shale	3280	blow 9 min. Rec. 10' drilling mud.
shale, Lansing	3340	ISIP 37#/30 min., FSIP 37#/30 min.,
lime, Kansas City	3380	IFP 18#, FFP 18#.
lime	3605	
shale & lime	3825	DST #5 4456-4462' Op 2 hrs. w/moderate
broken shale, lime, clay chert & sand	3880	blow. Rec. 75' muddy water w/specks of
shale & lime	3976	dark oil & 660' salt water. ISIP 1403#
Mississippian	3998	30 min., FSIP 1468#/45 min., IFP 46#,
Mississippian lime & shale	4018	FFP 364#.
lime, shale, chert	4040	
Mississippian	4085	
Mississippian lime & shale	4140	
lime, cherty & shale	4190	
Mississippian lime & shale	4265	
lime, shale, chert	4282	
Mississippian	4307	
Mississippian lime & shale	4323	
Kinderhook shale	4335	
chert	4350	
Kinderhook	4420	
shale & lime	4438	
shale	4446	
Simpson shale	4448	
Simpson sand	4456	
sand, hard	4460	
Simpson	4462	RTD
Total Depth		

TOPS:	SAMPLE	WELEX
Elgin Sandstone	2557	
Heebner	2735	
Brown Lime	3058	
Stalnaker Sandstone	3104	
Kansas City Limestone	3338	3338
Base Kansas City	3590	3590
Marmaton	3653	3653
Cherokee	3791	3791
Mississippian	3975	3975
Base Mississippian	4356	4356
Simpson Sandstone	4445	4445

DST #1 3405-3460' Op 1 hr. w/good steady
blow. Rec. 1780' gas in pipe, 360' heavily
oil & gas cut mud, 120' oil & gas cut salt
water, 240' salt water. ISIP 1385#/30 min.
FSIP 1358#/30 min., IFP 73#, FFP 300#.