


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANS, INC.
 Farm- Cole No. 2

SEC. 24 T. 31 R. 4W
 NW SE NW

Total Depth. 4480'
 Comm. 5-28-60 Comp. 6-12-60
 Shot or Treated.
 Contractor.
 Issued. 10-22-60

County Sumner
 KANSAS



Elevation. 1350' KB

Production. 43 BOPD

CASING:

8 5/8" 255' cem w/200 sx.
 4 1/2" 4479' cem w/100 sx.

Figures indicate Bottom of Formations.

shale, sand , shells 190
 shale, shells 510
 shale, shells, lime 860
 shale & lime 3410
 lime 3459
 shale & lime 3975
 lime 4322
 shale & lime 4417
 sand 4446
 shale & lime 4480 RTD
 Total Depth

TOPS:

Elgin Sand 2571
 Heebner Shale 2752
 Brown Lime 3079
 Stalnaker Sand 3137
 Kansas City Lime 3358
 Base Kansas City 3601
 Cherokee Shale 3801
 Mississippi 3980
 Kinderhook Shale 4325
 Simpson Sand 4416