

24 - 31 - 4W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Conrady No. 2

SEC. 24 T. 31 R. 4W
NW NE SW

Total Depth. 4443'
Comm. 6-27-60 Comp. 7-11-60
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 10-22-60

County Sumner
KANSAS



CASING:

8 5/8" 220' cem w/175 sx.

Elevation. 1342' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	220
shale & shells	795
shale & lime	1510
shale	2025
shale & lime	2215
shale	2445
shale & sand	2625
shale & lime	4057
lime	4333
shale & lime	4443 RTD
Total Depth	

TOPS: SAMPLE

Elgin Sand	2564
Heebner Shale	2746
Brown Lime	3070
Stalnaker Sand	3132
Kansas City Lime	3358
Base Kansas City	3607
Cherokee Shale	3803
Mississippi	3988
Kinderhook Shale	4329
Simpson Sand	4421

DRILL STEM TESTS:

#1 4415-4425 (Straddle) op 45 mins.,
rec. 5' of drilling mud. Weak blow,
dead in 4 mins. All pressures 0#.