

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

24 - 31 - 4W

Company- Pickrell Drilling Co.,
Farm- Jodon No. 1

SEC. 24 T. 31 R. 4W
NW NW SE

Total Depth. 4545'

Comm. 8-19-57


Comp. 9-5-57

Shot or Treated.

Contractor. Pickrell Drilling Co.,

Issued. 12-21-57

County Sumner KANSAS



CASING:

8 5/8" @ 200' W/150 sks. cem.

Elevation. 1338' RR.

Production. Dry

Figures indicate Bottom of Formations.

sand	20
red rock	200
shale	310
shale & shells & lime	860
lime & shale	1065
lime	1700
lime & shale	2485
lime & sand	2682
lime	2764
lime & shale	3046
lime	3150
lime, sand & shale	3240
lime & shale	3352
lime	4004
Mississippi	4043
lime	4073
lime & shale	4240
lime	4339
shale	4433
lime, shale & sand	4468
shale & sand	4515
lime, sand	4537
Arbuckle	4545
Total Depth	

Scout Tops:

Elgin Sand	2574
Heebner	2721
Brown Lime	3054
Stalnaker Sand	3126
Kansas City	3346
Base Kansas City	3595
Cherokee	3780
Mississippi	3976
Kinderhook	4331
Simpson	4422
A buckle	4511