


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PAN AMERICAN PETROLEUM CORP.
Farm- Winter Gas Unit No. 1
"C"

SEC. 27 T. 31 R. 40w
C SW NE
1980' N of SW, 1930' W of

Total Depth. 6050' PB 5610'
Comm. 10-10-60 Comp. 11-3-60
Shot or Treated.
Contractor. Barbour Drlg.
Issued. 2-4-61

County Morton
KANSAS



Elevation. 3304' Gr.

Production. 6,060,000 CFG

CASING:

8 5/8" 706' cem w/500 sx.
5 1/2" 6050' cem w/450 sx.

Figures Indicate Bottom of Formations.

surface clay, sand	215
sand	610
red bed, shale	740
red bed	1218
shale, Anhydrite	1745
lime, shale	2860
lime	2926
lime, shale	3018
lime	3088
lime, shale	3275
lime, sand	3373
lime, shale	3422
lime	3435
lime, shale	3535
lime	3635
lime, shale	3705
lime	3865
lime, shale	3935
lime	4115
lime, shale	4238
lime	4400
lime, shale	4615
lime	4835
lime, shale	5392
shale	5500
shale, lime, sand	5660
lime, shale	5746
lime	6050
Total Depth	
Plugged back to	5610
TOPS: SCOUT	
Council Grove	2684
Pennsylvania	3024
Topeka	3298
Mo.	3841
Des Moines	4662
Morrow	5258
Chester	5650
St. Gen.	5716
St. Louis	5846