

90116

MAP NO. 4-173W SEC. 25 TWP. 31S RGE. 40W

STATE Kans COUNTY Morton LOC. C SW/4

OPERATOR Pan American Pet Corp FT. FROM. LINE


NO. 1 FARM NAME Breeding GU "D" FT. FROM. LINE

Kinsler ELEV. 3263 EGR 3270 DF 3273E KB

R. 2/28/62 SPUD 3/1/62 COMP. 4/24/62

CONT. Big Chief Drlg Tools /GEOL.

COMPLETION RECORD NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD



NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

" " " " " "

" " " " " "

" " " " " "

D & A

D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBTD TD 6000

CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8 5/8" 1737 525

4 1/2" 5822 225

OPERATOR Pan American Pet Corp WELL NO. 1 Breeding GU "D" ELEV. 3273EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB tops & datums			Cg	2739	+ 534
			Penn	3086	+ 187
RTD (St L)	6000	-2727	Mo	3890	- 617
			Des M	4634	-1361
RTD 6000. SJ log.			Morr	5336	-2063
WLT #1 (Morr) 5666, op 1 hr,			Ches	5798	-2525
R 10' cc wtr, IBHP 0#/			St Gen	5886	-2613
15", SP 50#, FBHP 50#/15"			St L	5949	-2676
WLT #2 (Des M) 4677, op 1 hr, R 10' cc wtr, IBHP 0#/15",					
FBHP 50#/15".					
WLT #3 (Mo) 4291, fail.					
4 1/2" @ 5822 w/225 sx. MICT. CO 5822, 8/5664-66 (Morr)					
1000A, 15%, \$ 4 BF, 50% O + Ga 124 Mcfgpd/1 hr, Frac (10000					
GW x 8000# sd) \$ 77 BFW (Cut 5% O) Ga 108 Mcfgpd, PB5635, 12/					
5568-71 (Morr) 500MA, Frac(10000GA x 8000# sd) screen out,					
CO. PB 5500, 8/4812-14(Des M) \$ dry, 1000A (15%) Frac					
(10000GWx8000# sd)(750#walnut hulls, flush 3300 gw) \$ no sho					
tb\$ w/pkr 4765, 8/4996-98 (Des M) \$ 1/2 BFPH, No sho, PB 4688					
8/4676-78 (Des M) 1000A, \$ 1d, \$ 4 GFPH/NT, PB 4650, 8/					
4050-52 (Mo) 500A, (15%). No sho, D & A 4/12/62.					

COMPLETED

LIBERAL ELECTRIC LOG TOPS

3272 KB

Winfield 2426 (+846)
Council Grove 2682 (+590)
Heebner 3846 (-574)
Toronto 3860 (-588)
Lansing 3962 (-690)
Marmaton 4634 (-1362) WLT wtr
Morrow 5382 (-2110)
"S-2" 5564 (-2292) 0/18, NT
"S-3" 5664 (-2392) 11/20, WLT wtr
"S-3" 5728 (-2456) 0/22, NT
Chester 5772 (-2500)
Ste. Gen 5886 (-2614)
St. Louis 5978 (-2706)
TD 6000 D & A