

90115 *log*

E-3285 DF
ELEV. 3288RB, 3278 GL
Twp 31S Rge 40W

MAP NO. _____
STATE Kansas COUNTY Morton SEC. 23
OPERATOR Pan American Petroleum Corp. LOC. C SW NE
WELL NO. 1 FARM NAME Lutz Gas Unit "B" FT. FROM _____ LINE
POOL Kinsler FT. FROM _____ LINE
FR. 11-1-60 SPUD 11-26-60 COMP. 12-20-60
CONT./GEOL. Capitt Drlg. Tools

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			

D&A D & A (X)
SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
GOR. _____ GR. _____ PBD _____ TD 6000
CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8 5/8 723 500

OPERATOR Pan American Petr. WELL NO. #1 Lutz Gas Unit "B" ELEV. 3278 GL

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Council Grove	2750				
Pennsylvanian	3074				
Topeka	3362				
Missourian	3902				
Des Moines	4629				
Morrow	5382				
Chester	5774				
Ste. Genevieve	5876				
St. Louis	5960				

log in

RTD 5000, no cores or DST, Ran E-Logs.
#1 WLT @ 5682 (Morrow) op 90 mins, Rc 20,500 cc wtr, NS oil or gas, ISIBHP 1687/1 min, FSIBHP 1720/17 mins.
#2 WLT @ 3328, op 1 hr, Rc 250 cc wtr, no oil or gas, IBHP 562/39½ mins, FBHP less than 125/30 mins.
#3 WLT @ 2806, op 25 mins, Rc 20,500 cc wtr, no oil or gas, IBHP 440/1½ mins, FBHP 400/25 mins.
D&A
COMPLETE

2-11-60

LIBERAL ELECTRIC LOG TOPS

3288 KB

- Winfield 2414 (+874)
- Council Grove 2664 (+624) WLT - wtr, NS
- Topeka 3360 (-72)
- Heebner 3854 (-566)
- Toronto 3870 (-582)
- Lansing 3964 (-676)
- Marmaton 4634 (-1346)
- Morrow 5382 (-2094) tst NS
- "S-3" Sand 5678 (-2390) 4/9 (Wtr - NS)
- "S-3" Sand 5702 (-2414) 5/14
- Chester 5774 (-2486)
- St. Gen 5872 (-2584)
- St. Louis 5966 (-2678)
- TD 6000

M. J. W. "S-3" Sand 5678 (-2390) 4/9 (Wtr - NS)

Lo 33 5741 -2456 10/17

*247
2414
3661*