

90110

7-124W 8+ PERMANENT FILE 2077 TWP. 31S RGE. 40W  
 STATE Kans COUNTY Morton LOC. C NW SE  
 OPERATOR Pan American Pet. Corp.  
 WELL NO. 1 FARM NAME Brown Gas Unit "I" FT. FROM LINE  
 POOL Kinsler ELEV. 3322 GR 3328 DF 3331 KB  
 FR. 5/15/62 SPUD 5/14/62 COMP. 7/17/62  
 CONT. Prime Drlg. Co. /GEOL.

NAME PRODUCING INTERVAL COMPLETION RECORD - /GEOL.  
 FROM - TO PERF. W/HOLES TREATMENT RECORD

| a | b | c | d |
|---|---|---|---|
|   |   |   |   |
|   |   |   |   |
|   |   |   |   |
|   |   |   |   |

a I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.  
 b " " " " " "  
 c " " " " " "  
 d

D & A D & A ( )  
 SIPH FI TP # FI CPH SIBHP  
 GOR. GR. PBD TD 5700  
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.  
 8 5/8" @ 1627 800

OPERATOR Pan American Pet WELL NO. 1 Brown Gas Unit "I" ELEV. 3331 KB

| SAMPLE TOPS                                                | DEPTH | SUB SEA | ELEC. TOPS  | DEPTH     | SUB SEA |
|------------------------------------------------------------|-------|---------|-------------|-----------|---------|
| KB Tops & Datums                                           |       |         |             |           |         |
| RTD (Salem)                                                | 5700  | -2369   | Chase       | 2196      | +1135   |
|                                                            |       |         | CG          | 2462      | + 869   |
| RTD 5700. Log., 4 1/2" @                                   |       |         | Penn        | 2896      | + 435   |
| 5700 w/170 sx, CO 5669,                                    |       |         | Mo          | 3642      | - 311   |
| 16/5632-36 (Salem) Swb                                     |       |         | DesM        | 4316      | - 985   |
| dry, 500 A(no take)                                        |       |         | Morr        | 4913      | -1582   |
| Swb 51 BFW/11 hrs., PB                                     |       |         | Morr SD     | 4992-5013 | -1661   |
| 5610, Perf 8/5533-35                                       |       |         | Morr Marker | 5214      | -1883   |
| (St Lou) Swb 205 BFW/13                                    |       |         | Morr Sd     | 5278-94   | -1947   |
| hours, PB 5520, Perf                                       |       |         | Chester     | 5320      | -1989   |
| 8/5473-75 (St. Lou) Swb                                    |       |         | St. Gen     | 5349      | -2018   |
| dry, 500 acid, Swb 1d, Swb                                 |       |         | St. Lou     | 5464      | -2133   |
| 165 BFW/NS/11 hours.,                                      |       |         | Salem       | 5630      | -2299   |
| PB 5450, Perf 8/5289-91                                    |       |         | LTD         | N.A.      |         |
| (Morr) Swb dry, 1000 acid,                                 |       |         |             |           |         |
| (15%) Swb 1d, NS, Sq 5289-91, 100 sx, CO 5238, 8/5006-08   |       |         |             |           |         |
| (Morr) Swb dry, NS, Sq 50 sx, 8/5003-05 (Morr) 500 acid,   |       |         |             |           |         |
| Swb 1d, w/tr FW, Frac (10,000 GO x 8,000# sd) (500# alum   |       |         |             |           |         |
| pellets) Swb 250 BLO/14 hours, Swb 1-3/4 B 1d OPH/NW/8hrs. |       |         |             |           |         |

Plug @ 4940, Perf 8/4397-99 (Des MO), swb 48 BW w/scum oil/12 hrs,  
PB 4380, perf 8/4190-92 (Mo) A/500 (15%), swb 59 BFW/10 hrs,  
no show, D & A.

# LIBERAL ELECTRIC LOG TOPS

3331 KB

Winfield 2238 (+1093)  
Council Grove 2494 (+837)  
Topeka 3153 (+178)  
Heehner 3599 (-268)  
Lansing 3708 (-377) \$ 59 BFW/10 hrs  
Marmaton 4312 (-981) \$ 48 BW w;scum oil/12 hrs  
Morrow 4943 (-1612)  
"L" Sand 5001 (-1670) 11/11; \$ dry/NS  
"S-3" 5214 (-1883) 0/6  
"S-3" 5278 (-1847) 0/16; \$ NS  
Chester 5338 (-2007)  
Ste. Gen 5386 (-2055)  
St. Louis 5464 (-2133) \$ XW  
Spergen (Opr) 5630 (-2299)  
TD 5700 D & A