

90119

A-7-196

3326 KB

MAP NO. \_\_\_\_\_ ELEV. 3323 DF  
STATE Kansas COUNTY Morton SEC. 28 Twp 31 S Rge 40 W  
OPERATOR Pan American Petroleum Corporation LOC. C NE SW  
WELL NO. 1 FARM NAME Perkins GU FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
POOL Wildcat \* (PD 5500) FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
FR. 5-18-61 SPUD 5-5-61 COMP. 7-23-61

CONT./GEOL. Big Chief tools.

| COMPLETION RECORD       |                  |                   |                  |
|-------------------------|------------------|-------------------|------------------|
| NAME PRODUCING INTERVAL | FROM - TO        | PERF. W/HOLES     | TREATMENT RECORD |
| a. <u>Des Moines</u>    | <u>4322-4584</u> | <u>52</u>         | <u>13,500 Ac</u> |
| b. <u>Mississippian</u> | <u>5401-57</u>   | <u>36</u>         | <u>7,000 Ac</u>  |
| c. _____                | _____            | _____             | _____            |
| d. _____                | _____            | _____             | _____            |
| d I. P. OIL/DIST.       | WTR. <u>WHOF</u> | GAS <u>13,400</u> | M.C.F.P.D. _____ |
| b. "                    | " <u>WHOF</u>    | " <u>19,600</u>   | " _____          |
| c. "                    | " _____          | " _____           | " _____          |
| d. _____                | _____            | _____             | _____            |

|  |  |  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |

SIP# 1006(a):1188 (b) FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_  
GOR. \_\_\_\_\_ GR. \_\_\_\_\_ PSTD 5512 TD 6258

| CASING - CEMENT RECORD |             | Cement     |       |
|------------------------|-------------|------------|-------|
| SIZE                   | DEPTH       | W/SAX.     | DEPTH |
| <u>10-3/4"</u>         | <u>712</u>  | <u>700</u> | _____ |
| <u>5 1/2"</u>          | <u>5549</u> | <u>600</u> | _____ |

OPERATOR Pan American Pet WELL NO. 1 Perkins GU ELEV. 3326 KB

| SAMPLE TOPS     | DEPTH | SUB SEA | ELEC. TOPS     | DEPTH | SUB SEA |
|-----------------|-------|---------|----------------|-------|---------|
| Warsaw          | 5764  |         | Council Grove  | 2428  | +898    |
| Osage           | 5796  |         | Pennsylvanian  | 2857  |         |
| Kinderhook Lime | 5980  |         | Missouri       | 3570  |         |
| Viola           | 6031  |         | Des Moines     | 4257  |         |
|                 |       |         | Morrow         | 4850  | -1524   |
|                 |       |         | Chester        | 5212  | -1886   |
|                 |       |         | Ste. Genevieve | 5238  |         |
|                 |       |         | St. Louis      | 5345  |         |
|                 |       |         | Warsaw         | 5770  |         |
|                 |       |         | Osage          | 5806  |         |
|                 |       |         | Kinderhook     | 5986  |         |
|                 |       |         | Viola          | 6042  |         |
|                 |       |         | Arbuckle       | 6144  |         |

\* Change pool from Kinsler to Wildcat (deeper pool test).  
Spud 5-15-61. 10-3/4" @ 712 w/700 sx. @ 5550, logs (Sj) to 5554. 5 1/2" @ 5549 w/600 sx.  
RTD 6250, logs to 6258. Lost pt log tool, top fish 5628. MICT.  
Did not rec fish @ 5628. Set cem plug @ 5570.  
OH fr 5549-70. Swb 1d/NS. 500 Ac. Swb 1d/NS. Set BP @ 5512.

A-7-196

SHEET NO. 2

MAP NO. \_\_\_\_\_

STATE Kansas COUNTY Morton SEC. 28 Twp 31 S Rge 40W

OPERATOR Pan Am Petroleum LOC. C NE SW

WELL NO. 1 FARM NAME Perkins GU

P/12/5455-57. Swb 1d. 6 hr ga 1400 MCF (5½" csg).  
P/12/5427-29, 12/5401-03. 30 min BD 1500 MCF (5½" csg). 7000-15% Ac (5401-57). 7 hr ga 12,643 MCF, (5½" csg). 24 hr ga 19,000 MCF (5½" csg). Set model D pkr w/plug @ 5375.

P/8/4582-84. Ga 5000 MCF/5 hrs.

P/12/4412-15, 8/4393-95, 16/4322-26. Trt (4322-4584) w/3600-15% Ac w/12 sealer balls. 3300-15% Ac w/12 sealer balls. 6600-15%. 12 hr ga 13,373 MCF + 1 BLPH (5½" csg). 2-3/8" in pkr @ 5375. From 5401-57 ga 10,158 MCF + ½ BLPH. From 4322-4584, ga 6875 MCF (Had communication). Killed well w/450 BW.

Re-P/8/4582-84. Re-set 2-3/8" tbg @ 5375. From 4322-4584. 12 hr ga 4320 MCF + 15 BLPH. 14 hr SIP 1178. From 5401-57. 8 hr ga 8000 MCF + 5 BLPH, SITP 1188, SICP 1000.

IP WHOF 13,400 MCF, SICP 1006, est del 4,100 MCF from Des Moines (4322-4584).

OPERATOR Pan Am Petroleum

WELL NO. 1 Perkins GU

IP WHOF 19,600 MCF, 2" tbg, SITP 1188, est del 7100 MCF from Missiissippian (5401-57).

Dual Completion

COMPLETE 7-23-61

LIBERAL LOG TOPS

3326 KB

Winfield 2212 (+1114)

Heebner 3532 (-206)

Toronto 3544 (-218)

Lansing 3634 (-308)

Marmaton 4254 (-928)  $\phi$  13.4 M

Morrow 4842 (-1516)

Lo "S<sub>3</sub>" Sand 5162 (-1836) 2/8; NT

Chester 5204 (-1878)

Ste. Gen 5236 (-1910)

St. Louis 5332 (-2006)  $\phi$  19.6 M

RTD 6250 (- ELog TD 5555

Tops reported by Opr. - not logged

Warsaw 5770

Osage 5806

Kinderhook 5986

Viola 6042

Arbuckle 6144

up S<sub>3</sub> 5096 - 1770 of 10 NT

KSL

mor 4860

sd 3290 - 5305

5310 - 24