

AP2#15-129-20718

MUSTANG DRILLING & EXPLORATION, INC.

Steckel Farms 1-4

Morton County, KS

SE NW NE 4 - 31^S - 4, W

DST #1 5405-20 (30-45-60-90)

IHP 2646, IFP 154/143, ISIP 1375, FFP 188/176,
FSIP 1375, FHP 2624

Temp 148°

Strong blow, gas to surface in 7 minutes.

1st 5 min gauged 269 MCF

next 5 min gauged 301 MCF

next 5 min gauged 324 MCF

10 min gauged 339 MCF

Second Open:

1st 5 min gauged 301 MCF

2nd 5 min gauged 342 MCF

10 min gauged 378 MCF

next 10 min gauged 395 MCF

next 10 min gauged 441 MCF, still building.

Rec: 65' heavy drilling mud, tool slid 8',
test chart indicated plugging on 1st open.