


7-125W + 81 PERMANENT FILE COPY SEC. 18 TWP. 31S RGE. 41W
 MAP NO. 81
 STATE Kans COUNTY Morton LOC. App C NE/4
 OPERATOR Pet. Inc. 1250 FT. FROM N LINE
 WELL NO. 1 FARM NAME Baughman 1250 FT. FROM E LINE
 TOOL Sparks ELEV. 3435 E GR. 3440 E DF 3442 KB
 9/28/61 SPUD 9/29/61 COMP. 7/17/62
 CONT. Garvey Drlg. Tools /GEOL.
 NAME PRODUCING INTERVAL COMPLETION RECORD FROM -- TO PERF. W/HOLES TREATMENT RECORD
 a _____
 b _____
 c _____
 d _____
 e I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
 b " " " " " "
 c " " " " " "
 d _____
 D & A D & A ()
 SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PSTD _____ TD 5560
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
 8 5/8" @ 151 675
 2 7/8" @ 3069 175



OPERATOR Pet. Inc.			WELL NO. 1 Baughman		ELEV. 3442 KB	
SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA	
KB tops & Datums						
B/Cimm	1519	+1923	B/Anh	1536	+1906	
Neva	2765	+ 677	Kri	2177	+1265	
Waub	2876	+ 566	Winf	2235	+1207	
Top	3162	+ 280	Waub	2876	+ 566	
Lans	3703	- 261	Top	3162	+ 280	
Marm	4159	- 717	GreenwoodLans	3486	- 44	
Morr Ch	4850	-1408	Lans	3700	- 258	
Morr "G" Sd	5180-5200-1738		Marm	4159	- 717	
2nd Morr sd	5212-23	-1770	Morr	4846	-1404	
Morr sd	5234-55	-1792	Morr "G"sd	5232-74	-1790	
			Keys	5324-40	-1882	
RTD(StLou)	5560	-2118	St. Gen	5340	-1898	
			St. Lou	5456	-2014	
			LTD(St.Lou)	5555	-2113	

DST #1 (Neva) 2766-2871, Op 1 hr., R 95' mud, IBHP 710# 30", IFP 15#, FFP 50#, FBHP 575#/30".

DST #2 (Waub) 2878-2925, Op 1 hr., GTS/2", Ga 1710 MCFGPD/5", Ga 1860 MCFGPD/15", Ga 1930 MCFGPD/25", Ga 2060 MCFGPD & Stab 40", R 140' Mud, IBHP 580#/20".

FP 465-465, FBHP 550/20:
DST (Top) 3166-3310, op 1 hr, rec 450' M + 90' SXCM, FP 190-355,
BHP 600-565/40:
DST (Mor Sd) 5174-5223, failed:
DST (Mor) 5172-5223, op 40 min, rec 15' Mud, FP 0-0, BHP 0-0/30:
DST (Mor) 5217-63, op 1½ hrs, GTS/5", g 62 MCF/5", g 44 MCF/10",
g 22 MCF/15" & stab, rec 370' HGCM + 180' XWCM, FP 90-120,
BHP 1220-1185/30:
DST (Ste. Gen) 5339-48, op 1½ hrs, rec 35' SO&GCM + 180' SO&GCWM,
FP 0-95, BHP 1195-1140/30:
RTD 5560, ran log;
WLT (Keyes) 5329-31½, op 1½ hrs, rec 20,800 cc wtr, IBHP 1250/7,
FSIP 1260/20:
PB 3736/25 sx cem, 2 7/8" tbg w/175 sx;
Perf 20/2912-16 (Wab), g 200 MCF (Nat) w/fine spray wtr, A/250,
g 250 MCF, 5/2884-88, 11/2890-2900, g 250 MCF, ran 2" tbg w/pkr @
2829, A/10,000, flo 700 MCF + mist of flu, g 882 MCF/6 hrs, A/
10,000 + 10 balls, g 500 MCF/6 hrs, g 800 MCF + est. 1½-2 B of
BS&WPH. D & A. 2/26/62.

LIBERAL ELECTRIC LOG TOPS

Winfield 2234 (+1210)
Council Grove 2464 (+980) g 500 MCF (Wab)
Topeka 3161 (+282) tst XWCM
Heebner 3586 (-141)
Lansing 3690 (-254)
Marmaton 4246 (-802)
Morrow 4862 (-1418)
"S-3" 5232 (-1788) 40/40; tst G+XW
Keyes 5324 (-1880) 13/15; WLT wtr
Ste. Gen 5340 (-1896) tst SO&WCM
St. Louis 5456 (-2012)
TD 5650