

90176

A-5-191

MAP NO. K-82 ELEV. 3430 DF  
 STATE Kansas COUNTY Morton SEC. 20 Twp 31 S Rge 41 W  
 OPERATOR Thomas-Brewer LOC. NW NE SW  
 WELL NO. 1 FARM NAME Harrison FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 DOL. Unnamed FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 PR. 3-17-61 SPUD. 3-13-61 COMP. 5-9-61

CONT./GEOL. Bennett & Roberts + Russell


COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Wabaunsee</u>	<u>2855-94</u>	<u>36</u>	<u>4500 Ac.</u>
b			
c			
d			

d I. P. OIL/DIST. \_\_\_\_\_ WTR. COF GAS 2350 M.C.F.P.D. \_\_\_\_\_ CHK. 4 pt HRS. \_\_\_\_\_  
 b " " " " " " " "  
 c " " " " " " " "  
 d \_\_\_\_\_

SIP# 425 FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_  
 GOR. \_\_\_\_\_ GR. \_\_\_\_\_ PBDT 2931 TD 5350

CASING - CEMENT RECORD			
SIZE	DEPTH	W/SAX.	SIZE
<u>8-5/8"</u>	<u>1432</u>	<u>675</u>	
<u>4 1/2"</u>	<u>2960</u>	<u>100</u>	

OPERATOR Thomas-Brewer WELL NO. 1 Harrison ELEV. 3430 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Herrington	2206	
			Wabaunsee	2856	
			Morrow	4928	
			Morrow Sand	5152	
			Keyes	5222	
			Mississippian	5312	

Spud 3-13-61. 8-5/8" @ 1432 w/675 sx.  
 DST # 1 (Morr) 5146-80, pkr failed.  
 DST # 2 (Morr) 5152-80, op 1 hr, rec 180' M, FP 84-105, SIP 569/30 mins.  
 RTD 5350, logs.  
 WLT # 1 (Keyes) @ 5247, op 1 hr, rec 5000 cc SW, ISIP 1250/15 mins, FSIP 1280/15 mins.  
 WLT # 2 (Keyes) @ 5235, op 33 mins, rec 220 cc SW, ISIP 0/15 mins, FSIP 0/15 mins.  
 WLT # 3 (Morr) @ 5169 1/2, op 95 mins, rec 2500 cc FtW, ISIP 1280/31 mins, FSIP 1250/25 mins.  
 WLT # 4 (Wab) @ 2897, op 11 mins, rec 22.9 CFG + 160 cc FtW, ISIP 488, FSIP 500.  
 WLT # 5 (Herr) @ 2158, op 90 mins, no rec, ISIP 0, FSIP 600.

4½" @ 2960/100 sxs. MICT, CO 2931.

P 4/2901-02, SQ/150 sx. p 4/2879-80, SQ/150 sx. P 4/2852-53, SQ/150 sx. P 4/2847-48, SQ/150 sx.

P 16/2890-94. 250 MA. Swb ld/NS. SQ 2890-94/150 sx. CO  
Re-P 16/2890-94, P 16/2870-74, 4/2855-56. 4500 MA. Ga 7700  
MCF + 4 BLPH. 2" tbg @ 2844. g 1,780 MCF.

IP 4 pt COF 2,350 MCF, SIP 425 from Wabaunsee (2855-94).

LIBERAL TOPS

3436 KB

Topeka 3126 (+310)

Heebner 3562 (-126)

Lansing 3672 (-236)

Morrow 4824 (-1388) T 476', Tss 82'

"S-3" 5152 (-1716) 38/40, NS

"S-3" 5200 (-1764) 5/6, NT

Keyes 5220 (-1784) 34/36, WLT XW

Chester 5300 (-1864)

TD 5350