

State Ks. Field PATSY
 Company PEPL County MORTON
 Farm BEHM No. 1-21
 Sec. 21 Twp. 31 Range 41
 Spot CSW
 Contractor Shaeffer
 Remarks P.D. Miss
 Comm. 9-10-58 Comp.
 Elev. DF 3417 GL 3410 KB TD 5380 PB
 Pay



I.P. Press.
 Casing Record: 13 3/8 7"
 20" 10 3/4 7 1/2" 5288/200
 16" 8 5/8 2297/400

<u>MIRT</u>	Sample	Log
~~SEP 17~~ ~~2735~~ ~~SEP 24~~ ~~4448~~ OCT 1 E 5205 -56 rec 51' 8' sh 1 1/2' sd 3' sd shaly 23' sd w/odor 11' sd w/shale of DST #1 5207 -56 op 25" rec 1890' 905 in ϕ pipe + 235' BCM + 95' SGCM with Trm O. FP 150 - 190 BHP 1100/20" ~~WOC.~~		~~Unb~~ ~~+552~~ 2865 ~~Top~~ ~~+283~~ 3134 ~~G.W. lens~~ ~~-59~~ 3476 ~~Lens~~ ~~-272~~ 3689 ~~Mar~~ ~~+848~~ 4265 ~~Chad~~ ~~-1011~~ 4428 ~~Mar~~ ~~-1236~~ 4653 ' ~~-1601~~ (11') u Mor zone 5019 ~~-1655~~ 29 u Mor sd 5072 ~~-1721~~ (5') 80 Mored 5138- (71') 5209 ~~-1801~~ 5218 (56') 74 ~~-1925~~ 6342 basal ~~-1934~~ (9') 51 Miss 5351

(over)

E 5256-75

rec 19'

3" shale

18 1/2' sd, bld oil

3" sh

DST#2 5254-75 op 1 hr

rec 990' gc m x w FP 0-990

BH 1310/20" ~~4 5275~~

OCT 8 E 5276-5310 rec 39'

34' sh.

E 5320-56 rec 10' sh.

E 5346-70 rec 29'

8' ss w/o + pan

1/2' sh

1/2' cong.

4' ls. shly

3/4' sh

7' ls

3' sh

1' ls

DST 5348-70 op 80" rec 30'

slty mud 390' x wtr FP 110-486

BHP 1350/10'

RTD 5380 S; logs

OCT 15 MICT P40/5224-34

A/1000 sub 4 1/2 BXWPH W 66

p1 3100 ~~prop to prop~~

OCT 22 P20/5072-77 A/1000 sub 1d N8

plg @ 4090 P8/3994-98 56/4025-53

A/5000 sub 1d N.S. plg @ 3260

P80/3248-50 sg/185 CO 3219

? P16/3137-45 14/3104-11

6/3086-89 10/3072-77 6/3062-65

8/3055-59 A/3000 subg 4 BWP11

OCT 29 p1 @ 3020 P20/2985-95

6/2896-99 12/2878-84 A/2000

sub 4 BXWPH w/ssg plg @ 2889


cont.

State Ks. Field _____
 Company PEPL County _____
 Farm Behm No. 1-21
 Sec. _____ Twp. _____ Range _____

Spot _____

Contractor _____

Remarks _____



Comm. _____ Comp. _____

Elev. _____ DF _____ GL _____ KB _____ TD _____ PB _____

Pay _____

_____ I.P. _____ Press. _____

Casing Record: 13 $\frac{3}{8}$ _____ 7" _____

20" _____ 10 $\frac{3}{4}$ _____ 5 $\frac{1}{2}$ " _____

16" _____ 8 $\frac{5}{8}$ _____

	Sample	Log
swb 3 BXWPH		G/R top 2151
w/ 9d sg. pull		Kri 2217
pl fm 2889		Win 2217
pull 4 $\frac{1}{2}$ " T pl @		
2270, G/R,		
P40/2217-27 A/1000		
swb 2B m xw PH N.S.		
pl @ 2180 P20/2159-59		
A/1000 swb		
NOV 5 swb N.S. P40/2165-75		
A/1000 swb N.S.		
D E H		

AMARILLO TOPS

3410 GL

Topeka 3133 (+277)

Heebner 3581 (-171)

Lansing 3688 (-278)

Morrow 4860 (-1450) T 691', Tss 94'

"S-2" Sd 5070 (-1660) 0/9, NS

"S-3" Sd 5188 (-1778) 20/22, NT, looks wet

Keyes 5218 (-1808) 45/53, SSG&O + XW

Keyes 5341 (-1931) 9/10, Tst'd XW

Chester 5351 (-1941) 9/10, tst'd XW