

Field Sparks
 State Kansas County Morton
 Company Huber Oil Co.
 Farm Collingwood Well No. 1
 Sec. 11 Twp. 31S Range 42W
 fr N fr E fr S fr W
 of C NE
 Contractor Holm Drlg.
 Remarks Carter DHM
 Comm. 5-19-56 Comp. 6/20/56
 Elev. 3474 DF 3K T. D. 5320 P. B.
 Pay 5202-30 5241-51

I. P. 3,310 MCF R 51TP 1025 #
 Casing Record: 13 3/8 7
 20 10 3/4 5 1/2 5321 / 260
 16 8 5/8 1520/750

	WOC.	Tops
MAY 30	TO @ 2968 - find	Mon 4878
re	3225	MML 5.5144
JUN 6	5185-	"6" sd 5200-30
	5188	Key 5239
JUN 13	5185-5235	Miss 5280
11' sh.		Mon 4873
1' sd. 12 1/2" shly Tite		"6" sd 5207
3' sh.		Key 5241
1' sdly sh.		Miss 5289
9' sh.		
19' sd. cong. gdpot. (oil ST 5310-14)		
1' shale		
10' sd. Tite		
5' sh.		
DST 5192-5235 op 1 hr. 9TS 6"		
up 10" g 926 MCF 1 hr. 1,300 MCF		
re 350' gcm. FP 190 → 230 BH 1230/30		
42 5235-59 re 24'		
9' sd. fr. por.		
9' shly sd. hd. lite n por		

6' sd. m. gr. ft. to gdpol.
DST 5236-59 op 1 hr. gts 4" g 1 hr.
1,540 MCF net 300' gcm. +60' mud w oil
apts +60' msw. FP 225→450 BH 1300/30
DST 5258-5320 - op 1 hr. ft to wdk blo
net 200' very sli cut watery mud +400'
sw. FP 200→360 BH 1100/15
RTD 5320 ran a/c 5327 at 5 1/2
5321/200 mict
JUN 20 RUCT CO to 5293 TANBR pf 4/5279-80
g 3 hrs ^{made} 4-5 bsuph g w 200
CO to ? pf 4/5250-51 NS pf 40/5241-51
made cut 4,000 MCF g 3 hrs g 4,248 MCF
5 1/2 bds 4,16'. pf 16/5226-30 2 hrs
5,284 MCF. pf 80/5207-27 2 hr BD g
6,101 MCF A/400m g 6,101 MCF. frac
1000/0 frac/10,000 ad/10,000 - shut to
5267 subbed in 9 MBD 2,530 thru
tubing SICP 1005# SITP 1025#
op 1 hr. g 3,310 MCF thru tubing.

¢