

AUG 28 1971

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

33.31-5W


ELEVATION: 1297'KB

SHORT #1

C SE SE, SEC. 33-31E-5W  
Harper County, Kansas

DRY/Simp.

KANSAS



Commenced: August 13, 1971  
Completed: August 24, 1971

OPERATOR: KEENER OIL CO.

DEPTH		FORMATION	REMARKS
From	To		
0	35	Sand	Ran 11 joints of used 8 5/8" casing
35	236	Redbed	Set @ 231' cement w/200 sbs common
236	400	Redbed and Shale	2% Gel-3% C.C.
400	876	Shale and Shells	P.D. @ 12:15 AM 8/14/1971
876		Anhydrite	Job by Halliburton
876	3560	Shale and Lime	
3560	4537	Lime	
4537	4658	Shale	
4658	4700	Sand	
4700	TD		Dry and Abandoned

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SE, Section 33-31E-5W, Harper County, Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
James S. Sutton II

STATE OF KANSAS )  
                          ) SS  
AUG. 29, 1971

LOG TOPS:

Iatan	3306
Stal	3315
Kansas City	3558
B " "	3799
Mississippi	4207
KH	4551
Simpson Sd	4653
2nd " "	4687

DST (1) 4655-60