


KANSAS GEOLOGICAL SOCIETY
 508 East Murdock
 Wichita, Kansas
 DEC 30 1971

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

34-31-SW
 S/2 CNE-SW
 34-31-5W



COSLETT #2
 150' S of C NE SW Sec. 34-31S-5
 Harper County, Kansas

50 BopD
 EL 1319KB

Commenced: September 8, 1971
 Completed: September 19, 1971

Operator: OASIS PETROLEUM INC.

DEPTH		FORMATION	REMARKS	
From	To			
0	30	Clay and Sand	Ran 11 joints of used 28# 8 5/8" casing L.D. @ 245' cement w/200 sks HA5 Posmix PD @ 10 PM 9/8/71 Cement Circ. Job by Howco Centralizer 5' below collar on shoe joint.	
30	400	Redbed and shale		
400	810	Shale and shells		
810	870	Shale		
870	1417	Shale and lime		
1417	1910	Lime and shale		
1910	3405	Shale and lime		
3405	3560	Lime and shale		
3560	4579	Lime		
4579	4652	Shale		
4652	4660	Sand		
4660	TD			Ran 136 joints of used 5 1/2" 15# LD @ 4659' - 6' off bottom cemented w/75 sks salt sat Poz P.D. @ 10 AM 9/19/71 Job by Howco

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 Marjorie Hall, Notary Public

My commission expires Nov. 29, 1971

LOG TOPS	DEPTH
STAL SD	3330
KC	3559
BLK SH	3697
CHER	3986
MISS	4207
KH	4556
SIMP	4654
RTD	4662