


don't repl

State Ks. Field \_\_\_\_\_  
 Company MAGNOLIA Petr. County COMANCHE  
 Farm MABEL ROBINSON No. \_\_\_\_\_  
 Sec. 5 Twp. 31 S Range 18 W  
 Spot 660 ft N  
125 " W C 1/2 NE NW  
 Contractor CAPITI  
 Remarks P.D. 5200'



Comm. 4-24-58 Comp. 6-25-58  
 Elev. DF 2155 GL KB TD 5140 PB 5045  
 Pay Miss 5037-43 GOR 2724:1  
pump I.P. 98 BOPD + 17 BSW/PD sty 36°  
 Press. \_\_\_\_\_

Casing Record: 13 3/8 \_\_\_\_\_ 7"  
 20" \_\_\_\_\_ 10 3/4 \_\_\_\_\_ 5 1/2" 5139/250  
 16" \_\_\_\_\_ 8 5/8 528/400  
509/250

	Sample	Log
<u>sand cag</u>		
<u>TTD. 425 &amp; fish.</u>	LAN 4405	LAN 4407
<u>MAY 7 couldn't see "</u>	Miss 5038	Miss 5037
<u>skid rig 25' W.</u>		Well 1841
<u>re-squid 428-58</u>		CHASE 2477
<u>\$3160</u>		C.G. 2870
<u>MAY 11 \$4725</u>		ADMIRE 3172
<u>MAY 21 5034-70 fail</u>		SHAW 3650
<u>DST 5021-70 "</u>		MARM 4844
<u>DST 5070-95</u>		
<u>op. 1' Rec 93'</u>		
<u>water mud w/ oil</u>		
<u>specks</u>		
<u>EP 40-80</u>		
<u>BHP 1450/1'</u>		
<u>T.T.D. 5095</u>		
<u>stop DST 5022-69 fail</u>		
<u>DST (st. ph) 5041-69</u>		
<u>gts 15" - test, Rec 100' GCM</u>		
<u>w/ oil specks + 90' 0+GCM +</u>		
<u>180' #0+GCM, EP 70-125</u>		
<u>SIP 1025/1'</u>		
<u>RTD 5140, Si, cag</u>		
<u>WOC</u>		

MAY 27 RUCT, C.O., GR

P/5 5029-30, SQ w/ 25 BX  
C.O. 5100

P/44 JUN 1 15071-82, thg 5068, Subg  
Surd 2 1/2 BNO + 22 BxW-14  
" 1 " + 6 " - 1

plug 5068  
P/720 5048-66, Surd W. + 30 BNO +  
22 BSW-14  
Surd 2 1/2 BNO + 3 1/2 BW-1

JUN 11 Surd 15 BNO + 11 BSW-7

P/24 5037-43 thg w/et plus  
5027 + 5045, Surd 14 BNO + 9 BSW-4  
Ac 1000, Surd 9 BNO + 4 Bcut + 2 BSW-2  
flod 2 1/2 BNO + 1 BSW-1, died  
Surd 24 BNO + 14 BSW-7

JUN 18 prep POP 59 BNO + 16 BSW-24

GOR 2440:1  
prep 42 BNO + 19 BSW-24  
Tstg

JUN 25

E prep 98 BOPD + 17 BSWPD  
GOR 2724 : 1, 85 36°