

15-077-20403

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG

API No. 15 — 077 — 20,403
County Number

S. 9 T. 31S R. 6 E
Loc. 1927' FSL & 1927' FWL
County Harper

Operator
Texas Oil & Gas Corp.

Address
200 West Douglas, Suite 300, Wichita, Kansas 67202


Well No. Lease Name
1 Stevens "B"

Footage Location
1927 feet from (N) line 1927 feet from (E) line

Principal Contractor Geologist
Xplor Drilling Company High Plains Consulting Ltd.

Spud Date Total Depth P.B.T.D.
3-7-77 4742' N/A

Date Completed Oil Purchaser
3-19-77 N/A



Elev.: Gr. 1506
DF 1511' KB 1514'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	227'	Common	255	2% Gel, 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	N/A	N/A	N/A

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production N/A	Producing method (flowing, pumping, gas lift, etc.) N/A				
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls.	Gas N/A MCF	Water N/A bbls.	Gas-oil ratio N/A	CFPB
Disposition of gas (vented, used on lease or sold) N/A			Producing interval(s) N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Stevens "B" Dry Hole

S 9 T 31S R 6 E


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	1344	+170		
Towanda	1478	+36		
Florence	1576	-62		
Wreford	1704	-190		
Beattie	1858	-344		
Cottonwood	1890	-376		
Fall City	2152	-638		
Indian Cave	2178	-664		
Wabaunsee	2225	-711		
Tarkio	2438	-924		
Howard	2638	-1124		
Topeka	2836	-1322		
Elgin	3028	-1514		
Heebner	3180	-1666		
Amazonia	3233	-1719		
Iatan	3417	-1903		
Stalnaker	3508	-1006		
Kansas City	3722	-2208		
Swope	3870	-2356		
Hertha	3906	-2392		
B/KC	3960	-2446		
Cherokee	4157	-2643		
Mississippi	4318	-2804		
Simpson	4719	-3205		
TD	4742	-3228		
DST #1, 3031-64', (Elgin) w/results as follows: IFP/30": 50-341#, weak to strong blow; ISIP/60": 1267#; FFP/45": 351-590#, strong blow thru-out; FSIP/90": 1277#; Rec 62' MW, 1054' SW.				
DST #2, 4325-40', (Mississippi) w/results as follows: IFP/30": 42-52#; ISIP/60": 1434#; FFP/45": 52-52#, GTS 25 @ 5 MCFD; FSIP/90": 1445#; Rec 90' GCM.				
DST #3, 4700-42', (Simpson) w/results as follows: IFP/30": 20-30#; ISIP/60": 1300#; FFP/45": 40-50#; FSIP/90": 1490#; Rec 65' DM.				
DST #4, 4346-67', (Mississippi) - Mis-run				
DST #5, 4346-67', (Mississippi) w/results as follows: IFP/30": 81-112#, strong blow thru-out; ISIP/60": 1529#; FFP/45": 327-327# strong blow thru-out; FSIP/90": 1529#; Rec 50' DM & 620' O&GCDM (hole in pipe, test inconclusive.)				
DST #6, 4346-47', (Mississippi) w/results as follows: IFP/100": 30-112#, strong blow thru-out, GTS 87", TSTM; ISIP/120": 1529#; No FFP or FSIP pressures; Rec 72' G&OCM, 62' OCWM, 124' wtr.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Harold A. Brown Signature District Geologist Title March 24, 1977 Date
---------------	---