

9-31-6W

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **PETROLEUM, INC.**

SEC. 9 T. 31 N. 6W  
 LOC. C NW NE

FARM **Wohlschlegel** NO. 2

TOTAL DEPTH **4753'**  
 COMM. **1-31-66** COMP. **2-18-66**  
 BSHOT OR TREATED  
 CONTRACTOR **Garvey Drilg. Co.**  
 ISSUED **5-14-66**

COUNTY **Harper**  
 KANSAS



CASING

20	10	
15	8 5/8	216' w/225 sx cem.
12	6	
13	5 1/2	4750' w/150 sx cem.

1522' D.F.  
 ELEVATION 1524' K.B.

PRODUCTION **Flo. 312**  
 BOPD, NW

FIGURES INDICATE BOTTOM OF FORMATIONS

20'	Clay and Sand
400'	Red Bed and Shale
645'	Shale
1325'	Shale and Lime
1765'	Lime
2160'	Lime and Shale
2485'	Shale and Lime
3405'	Lime and Shale
3581'	Sand
3585'	Lime
3702'	Shale with Lime
3719'	Shale and Lime
3754'	Lime
3810'	Lime and Shale
4015'	Lime
4349'	Lime and Shale
4585'	Lime and Chert
4690'	Lime and Shale
4735'	Simpson
4753'	Sandy Dolomite
4753'	RTD

TOPS:

Heebner	3179
Stalnaker sand	3416
Kansas City	3724
Hertha Lime	3897
Mississippi	4302
Kinderhook	4589
Simpson	4711

State of Kansas } ss  
 County of Barton }