

18-31-6W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- PHILLIPS PET. CO.  
Farm- Schultz "B" No. 1

SEC. 18 T. 31 R. 6W  
SW SW SW

Total Depth. 4817'  
Comm. 8-7-63 Comp. 8-27-63

County Harper  
KANSAS

Shot or Treated.  
Contractor. Garvey Drilling Co.  
Issued. 12-28-63



CASING:  
8 5/8" 631' cem w/250 sx.  
5 1/2" 4717' cem w/120 sx.

Elevation. 1476' KB

Production. 115 BO, 195BWPD

Figures Indicate Bottom of Formations.

redbed	20
redbed & sandy shale	390
redbed	530
shale & gypsum	636
shale	816
shale & shells	1110
lime	1850
shale	1900
shale & lime	2495
shale	2840
shale & lime	3230
lime & shale	3420
shale & lime	3625
lime & shale	3755
lime	3838
lime & chert	3873
lime	3920
lime & chert	3957
lime	4137
lime & shale	4207
shale & lime	4275
lime	4308
Miss. Chert & Lime	4390
lime & chert	4539
shale & lime	4669
Simpson	4755
Simpson Shale	4782
Arbuckle	4817 RTD
Total Depth	

TOPS: LOG	
Iatan	3521
Stalnaker	3635
Drum	3714
Base Kansas City	3930
Marmaton	3977
Cherokee	4123
Mississippi	4282
Kinderhook	4544
Chattanooga	4634

Simpson Sand	4667
Simpson Shale	4708
Arbuckle	4781

